

KANSAS GEOLOGICAL SOCIETY  
508 East Murdock  
Wichita, Kansas

MAY 22 1971

DRILLERS LOG

No. 1 Rempe

17-10-18W  
C SE SE NW

15-103-20300

CASING RECORD:

8 5/8" @ 209'  
w/150 sx cement

4 1/2" @ 3780'  
w/150 sx cement

TOTAL DEPTH: 3784'

COMPANY:

CONTRACTOR:

COMMENCED:

COMPLETED:

Hummon Oil, Inc.

Red Tiger Drilling Co.

April 2, 1971

April 13, 1971

DESCRIPTION:

SE SE NW

17-10S-18W

Rooks County,  
Kansas

ELEVATION: 2190' K.B.  
Temp. Abund.

FORMATION

FROM

TO

REMARKS

Sod & Sand	0	103
Sand & Shale	103	210
Shale & Red Bed	210	1010
Shale	1010	1055
D. Sand	1055	1255
Shale	1255	1590
Anhydrite	1590	1625
Shale	1625	2050
Shale & Lime	2050	3185
Lime	3185	3280
Shale & Lime	3280	3332
Lime	3332	3665
Lime, Chert, Congl.	3665	3760
Shale & Lime	3760	3767
Lime	3767	3774
Arbuckle	3774	3784

RECEIVED  
STATE CORPORATION COMMISSION  
APR 16 1971  
CONSERVATION DIVISION  
Wichita, Kansas


Log Log  
Jopka 3166  
Wellner 3380  
Jopka 3399  
LKC 3424  
" " 3552  
" " 3573  
" " 3589  
" " 3612  
BKC 3650  
Conglomerate 3669  
Simpson 3754  
" sd. 3766  
Arbuckle 3772

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice  
Jim Farrice

Subscribed and sworn to before me this 14th day of April, 1971.



Virginia K. Albert  
Notary Public

My Commission Expires: