

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00731

Company- DAVIS BROTHERS & TRANSIT CORP.
Farm- Orday "E" No. 1

SEC. 20 T. 10 R. 18W
SE SW NE

Total Depth. 3741'
Comm. 12-9-57 Comp. 12-20-57
Shot or Treated.
Contractor. Transit Corp.
Issued. 4-19-58

County Rooks
KANSAS



Elevation. 2149' DF

Production. 41 BOPD

CASING:

8 5/8" 196' w/125 sx cem.
5 1/2" 3738' w/200 sx cem.

Figures indicate Bottom of Formations.

shale, shells	120
sand	180
shale	450
shale, shells	1036
sand	1192
shale, shells	1525
Anhydrite	1560
shale	2011
shale, lime strks	2220
shale, lime	2565
shale, lime strks	2826
shale	2905
shale, lime	3036
shale	3144
shale, lime	3317
lime, shale strks	3346
Heebner	3349
lime	3553
lime, shale	3646
Conglomerate	3712
lime	3741
Total Depth	

TOPS:

Anhydrite (scout)	1525
Topeka	3128
Heebner	3346
Toronto	3361
Lansing	3387
B/Kansas City	3610 ?
Conglomerate chert	3642
Conglomerate shale (re-	3716
worked Simpson)	
Simpson	3726

DST #1 3376-3410 Open 54".
Weak blow 3". Rec. 14' mud
w/few oil specks. 20" ICIP
10#. 20" FCIP 20#. FP 5"-5#.

DST #2 3413-3460 Open 1 hr.
Rec. 296' muddy salt wtr.
20" ICIP 1290 #. 20" FCIP 885#,
FP 20#-155#.

DST #3 3516-3595 Open 30".
Weak blow 5". Rec. 26' mud
with slight show oil. 20"
ICIP 30# (malfunction). 20"
FCIP 885#. FP 7#-10#.

DST #4 3591-3712 Open 1 hr.
Rec. 264' SO&GCM, 124' HO&GCM
(15-20% oil), 64' VHO&GCM
(40% oil), 148' MCO (60% oil),
Oil very black and gassy. Est.
about 1 1/3 bbls. oil in the
600' fill up. 20" ICIP 1495#.
20" FCIP 1255#. FP 40#-290#.