

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

15-163-00703

Company- E.K. CAREY
Farm- V.R. Ordway

No. 1


SEC. 21 T. 10 R. 18W
C SW SW NE

Total Depth. 3730'
Comm. 8-2-54
Shot or Treated.
Contractor. E.K. Carey
Issued. 9-11-54

Comp. 8-13-54

County Rooks

KANSAS



CASING:
8 5/8" 220' w/140 sx cem.

Elevation. 2127' D.F.

Formations K.B.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	8
clay	45
sand	55
shale	80
brkn lime-shale	150
sdv shale	220
lime	221
shale-shales	650
sand	720
shale	860
shale-sand iron shells	970 ✓
sand	1160
shale-red bed	1490
anhydrite	1500
lime-shale	2175
lime	2300
lime-shale	3170
lime	3630
lime-shale	3675
lime-shale-chert	3730
Total Depth	

TOPS:

T opeka	3114
Heebner	3329
Toronto	3349
Lansing	3369
Shaley Conglomerate	3630
Cherty Conglomerate	3686
Conglomerate	3730

DST- 3517 to 3578 or 61' anchor,
open 1 hr. 3 min. Closed 20M
for BHP. Rec. 150' slightly
oil & gray cut mud, 60' wtr.
cut mud. BHP 1110# IFP 1875# FFP
650#.

DST- 3580 to 3630 or 50' anchor,
tool open 1 hr. Closed for
20M for BHP. Open with strong
blow, decreased in 40 min. to
weak blow. Rec. 275' drilling
mud. BHP 1570# FFP 100#.