

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-03647


Company. DAVIS BROS.-TRANSIT CORP.
Farm. Shepard "A" No. 1

SEC. 23 T. 10 R. 18W
SW SE NE

Total Depth. 3710'
Comm. 9-18-58 Comp. 9-30-58
Shot or Treated.
Contractor. Transit Corp.
Issued. 3-7-59

County Rooks

KANSAS



Elevation. 2113' KB

Production. 42 BOPD

CASING:

8 5/8" 177' cem w/130 sx.
4 1/2" 3703' cem w/260 sx.

Figures Indicate Bottom of Formations.

surface clay	40
shale	65
sand & gravel	75
shale	115
gravel & shale	145
shale	470
shale & shells	950
sand	1150
shale	1250
shale & pyrite	1370
shale	1448
Anhydrite	1483
shale	1945
lime	2060
lime & shale strks	2235
lime & shale	2370
shale	2465
lime & shale	2605
shale & lime	2672
shale	2760
lime & shale	2880
shale & lime	3090
lime & shale	3130
lime	3450
lime & chert	3488
lime	3605
lime & chert	3652
chert	3660
lime	3710
Total Depth	

TOPS:

Anhydrite	1451
Topeka	3082
Heebner	3303
Toronto	3320
Lansing-Kansas City	3344
Base Kansas City	3567
Conglomerate	3598
Simpson	3666
Arbuckle	3699

DST #1 3332-3412', op 2 hrs., rec. 120'
drilling mud. Few specks of free oil in
each tool joint. 20" IBHP 1280#, FBHP
950#, FP 70#-120#.

DST #2 3411-3498, op 2 hrs., rec. 502'
muddy salt water. 20" IBHP 1280#. FBHP
1155#, FP 90#-285#.

DST #3 3493-3570, op 2 hrs., rec. 145'
oily mud - 55% frothy oil, 45% drilling
fluid. 20" FBHP 380#, (climbing sharply).
FP 65#-100#.

Ran Schlumberger Laterolog Survey.