

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-00733


Company- DAVIS BROTHERS & TRANSIT CORP.
Farm- Shepard "C" No. 1

SEC. 24 T. 10 R. 18W
SW SW NW

Total Depth. 3648'
Comm. 11-29-57 Comp. 12-11-57
Shot or Treated.
Contractor. Transit Corp.
Issued. 4-19-58

County Rocks

KANSAS



Elevation. 2070' RB

Production. Pot. 39 BOPD

CASING:

8 5/8" 182' w/125 sx cem.
5 1/2" 3541' w/200 sx cem.

Figures indicate Bottom of Formations.

shale, surface clay	98
sand	152
shale	182
shale, shells	700
sand	1070
shale, sand strks	1150
red bed, shale	1398
Anhydrite	1435
shale, shells	1905
shale, lime	3145
lime	3189
lime, shale	3285
lime	3585
Conglomerate	3622
Arbuckle	3648
Total Depth	

TOPS:

Anhydrite (scout)	1398
Topeka	3030
Heebner	3247
Toronto	3263
Lansing	3288
B/Kansas City	3514
Conglomerate-chert	3544
Conglomerate sand	3593
Reworked Arbuckle	3622
Simpson shale	3628
Arbuckle	3641

DST #1 3278-3312 Open 1 hr.
Fair blow. Rec. 60' gas, 65'
M to HOCM. 20" ICIP 1195#,
20" FCIP 810#, FP 35#-50#.

DST #2 3311-3338 Open 1 hr.
Weak blow. Rec. 60' watery mud.
20" ICIP 1080#. 20" FCIP 890#.
FP 30#-65#.

DST #3 3332-3360 Open 1 hr.
Light blow throughout. Rec. 30'
VHOCM (35% oil), 100' OCM (10-15%
oil), 20' muddy wtr. 20" ICIP
1180#, 20" FCIP 1050#, FP 25#-80#.

DST #4 3405-3433 Open 1 hr. Weak
blow 9 mins. Rec. 20' muddy wtr.
20" ICIP 93#. 20" FCIP 80#. FP
10#-23#.

DST #5 3447-3495 Open 1 hr.
Weak blow. Rec. 55' VSOCM. 20"
ICIP 1185#. 20" FCIP 415# (not
maximum). FP 25 #-60#.