

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00732

Company- DAVIS BROS & TRANSIT CORP.
Farm- Shepard "G" No. 1

SEC. 25 T. 10 R. 18W
SW SE NW

Total Depth. 3675'
Comm. 5-24-58 Comp. 6-4-58
Shot or Treated.
Contractor. Transit Corp.
Issued. 9-20-58

County Rooks
KANSAS



CASING:
8 5/8" 176' cem w/130 sx.
4 1/2" 3674' cem w/250 sx.

Elevation. 2021' KB

Production. 15 BOPD

Figures indicate Bottom of Formations.

rock	55
clay & shale	90
sand	150
shale	300
shale & shells	597
sand	780
shale & shells	1338
anhydrite	1376
shale & shells	1875
shale & lime streaks	1925
lime & shale	2040
lime & shale streaks	2190
lime & shale	2300
shale & lime streaks	2420
lime & shale	2565
shale w/lime streaks	2660
shale	3014
lime & shale	3070
lime	3175
lime & shale	3485
lime & chert	3560
Conglomerate & chert	3563
shale & lime	3589
Simpson	3625
Arbuckle	3675 RTD
Total Depth	

TOPS:
Topeka 2995
Heebner 3214
Toronto 3230
Lansing 3256
Base Kansas City 3488
Conglomerate 3518
Simpson 3570
Simpson Dolomite 3574
Arbuckle Dolomite 3625

DST #1 3219-3276, op 1 hr, weak blow 12".
rec. 15' mud w/a few oil specks. 20"
ICIP 1295# (false?). 20" FCIP 50#.
FP 35# - 35#.

DST #2 3272-3325, op 1 hr, weak blow 5".
Recovered 8' mud, 20" ICIP 1245#, 20"
FCIP 360#, FP 24# - 35#.

DST #3 3320-3350, op 45". weak blow 12".
Rec. 11' mud, 20" ICIP 1255#, 20" FCIP
765#, FP 15#-25#.

DST #4 3393-3485, op 1 hr, strong blow,
rec. 405' HOCM, very slightly watery.
20" ICIP 1320#, 20" FCIP 1010#, FP 65#-
220#.