

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-06908

Company- DAVIS BROTHERS & TRANSIT CORPORATION
Farm- Shepard "K" No. 1

SEC. 26 T. 10 R. 18W
SE NW SW

Total Depth. 3846'
Comm. 3-2-59 Comp. 3-13-59
Shot or Treated.
Contractor. Transit Corporation.
Issued. 5-30-59

County Rocks KANSAS



Elevation. 2976' KB

Production. Dry

CASING:

8 5/8" @ 161' cen. w/130 sx.

Figures Indicate Bottom of Formations.

surface clay	5
post rock	40
shale	85
sand	115
shale	161
shale & shells	815
sand	912
shale & shells	1435
Anhydrite	1466
shale & shells	1840
shale	2040
lime & shale streaks	2170
salt & lime streaks	2245
lime & shale streaks	2310
lime	2350
shale & lime streaks	2415
shale	2450
shale w/lime streaks	2502
lime & shale	2625
shale & lime	2920
shale & lime streaks	3020
shale & lime	3162
lime	3585
lime & chert	3654
chert	3675
cherty Conglomerate	3763
Simpson shale	3818
Arbuckle	3846 RTD
Total Depth	

TOPS:

Anhydrite	1435
Topeka	3068
Heebner	3293
Toronto	3310
Lansing	3335
Base/Kansas City	3564
Conglomerate	3599
Simpson	3710
Arbuckle	3818

DST #1 - 3298-3410. Open 1 hr. Rec. 35' mud.
20" IBHP 1340# (slid tool). 30" FBHP
440#, still climbing. FP 0#-0#.

DST #2 - 3401-3485. Open 2 hrs. Rec. 245'
muddy salt water. 20" IBHP 1380#. 30"
FBHP 1040#. FP 0#-160#.

DST #3 - 3480-3578. Open 2 hrs. Rec. 180'
salt water. 20" IBHP 1280#. 30" FBHP 1060#.
FP 0#-190#.