

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

15-163-00345

COMPANY M & L OIL COMPANY

SEC. 26 T. 10 R. 18W
LOC. SW SW NE

FARM Wiesner

NO. 1

TOTAL DEPTH 3715

COMM. 3-18-51

COMP. 3-31-51


SHOT OR TREATED

CONTRACTOR C-G Drdg.

ISSUED 4-21-51

COUNTY Rooks

KANSAS



CASING

8 5/8" 220.16

ELEVATION 2111 R.B.

All meas. from the top of rotary bushing.

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

shale, shells, sand	805
sand	900
shale, shells	935
sand	1110
redbed	1455
anhyd.	1490
shale, shells	2010
lime, shale	3400
lime	3615
congl.	3660
congl.	3715
Total Depth	

Tops:

Topeka	3075
Heebner	3322
Toronto	3341
Lansing-K.C.	3365
Base K.C.	3589
Congl.	3627
Simpson (?)	3709

Porosity zones in L-K.C.

3417-3420; poor por., very rare stain.

3429-3433; " " " "

3441-3444; " " no "

3459-3462; fair " " "

3492-3497; poor " " "

3522-3527; samples cir. at 3527 had fair
odor, a tr. of free oil, and fair spotted
staining in poor to fair por. A D.S.T. at
3527 w/packer set at 3519 was open 35 mins.
& rec only 15' of mud w/no show of oil No
BHP was recorded.