

State Geological Survey
WICHITA BRANCH

CONTRACTOR'S WELL LOG

15-163-20828
28-10-18W

OPERATOR: John P. Jennings Oil Co.
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: Henn #1
LOCATION: NE SW NE Section 28-10S-18W
ROOKS COUNTY, KANSAS
SPUD DATE: July 14, 1978
COMPLETION DATE: July 23, 1978

0	261	Rock & shale
261	1420	Shale & sand
1420	1455	Anhydrite
1455	1785	Sand & shale
1785	3082	Shale & lime
3082	3339	Lime
3339	3380	Lime & shale
3380	3472	Shale & lime
3472	3480	Lime & shale
3480	3555	Lime
3555	3654	Shale & lime
3654	3670	Lime
	3670	Rotary Total Depth

Spud hole at 1:00 p.m., July 14, 1978. Drilled 261' of 12 $\frac{1}{4}$ " hole. Ran 6 jolts of 8-5/8" (28#) surface casing. Set at 256.13' with 165 sacks common cement, 3% CaCl, 2% gel. Cement did circulate. Plug was down at 8:00 p.m., July 14, 1978.

T.D. 3670'. Set first plug at 600' with 70 sacks, second plug at 240' with 20 sacks, top plug at 40' with 10 sacks. Cemented with 50/50 posmix, 6% Gel. Plug was down at 6:00 a.m., July 23, 1978. State Plugger, Leo Massey.

SAMPLE TOPS:

Anhydrite 1420' (+ 661)
B/Anhydrite 1455' (+ 626)

STATE OF KANSAS }
 } ss
COUNTY OF SEDGWICK }
 }

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Henn #1, NE SW NE Section 28-10S-18W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY

Jack L. Partridge
Jack L. Partridge