

KANSAS


WELL COMPLETION REPORT AND
DRILLER'S LOG

State Geological Survey

WICHITA, BRANCH 18 XXX
W

Loc. NE NW SW

County ROOKS

640 Acres
N

Locate well correctly

Elev.: Gr. 2015

DF 2018 KB 2020

API No. 15 — Rooks — 15-163-21,251
County Number

Operator

PRICE EXPLORATION COMPANY

Address

412 Mayo Building, Tulsa, Okla. 74103

Well No.

1

Lease Name

Andreson "E"

Footage Location

2310
feet from (N) (S) line990
feet from (E) (W) line

Principal Contractor

Shields Drilling Company

Geologist

C.K. Ottaway

Spud Date

2/21/81

Date Completed

3/1/81

Total Depth

3650

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8		250	Common	165 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
D & A					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator PRICE EXPLORATION COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole	
Well No. 1	Lease Name Andreson "E"		
S 29 T 10 R 18 W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Shale Shale and sand streaks Shale Anhydrite Shale Lime and shale Lime DST #1 3225-85 Op 60 SI 30 Rec. 5' Mud, blow died after 20 min. IHP 2561 psi. FHP 2281 psi. IFP 52 psi FFP 52 psi ISIP 66 psi DST #2 3390-3490 Op 60 SI 30 Rec. 15' Mud, blow died. IHP 1875 psi. FHP 1864 psi. IFP 51 psi. FFP 51 psi. ISIP 846 psi		253 300 1386 1417 1943 3026 3650 RTD	Topeka 3011 Heebner 3229 Toronto 3245 Lansing- Kansas City 3271 Base- Kansas City 3493 Marmaton Chert 3512 Conglomerate 3560 Simpson 3612 Arbuckle 3633 R.T.D. 3650 L.T.D. 3650 Electric Log Great Guns R.A. Guard Log
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<div style="text-align: right; margin-bottom: 5px;"> <i>Robert D. McKenna</i> _____ Signature </div> <div style="text-align: right; margin-bottom: 5px;"> Geologist _____ Title </div> <div style="text-align: right;"> 3/17/81 _____ Date </div>		

20121