

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-02636 ✓


Company- DAVIS BROS.-TRANSIT CORPORATION  
 Farm- Wilson "B" No. 2

SEC. 34 T. 10 R. 18W  
 SE SE SW

Total Depth. 3538'  
 Comm. 2-26-63 Comp. 3-5-63  
 Shot or Treated.  
 Contractor. Transit Corp.  
 Issued. 5-18-63

County Rocks.

KANSAS



CASING:  
 8 5/8" 182' cem w/125 sx.

Elevation. 2037' DF

Production. Dry

Figures Indicate Bottom of Formations.

surface soil & post rock	75
water sand	80
clay & grey shale	105
blue shale	182
shale	450
shale & shells	630
shale w/sand strks.	745
shale	890
sand	950
shale	1080
sand	1110
shale	1400
Anhydrite	1435
shale & shells	1650
shale	1750
shale & lime shells	1940
lime & shale	2090
lime	2420
lime & shale	2530
shale	2675
shale broken sand	2775
lime & shale	2900
shale w/lime strks.	3010
shale	3035
lime	3538
Total Depth	

TOPS: SAMPLE

Anhydrite	1400
Topeka	3034
Heebner	3257
Toronto	3272
Lansing	3299
"A" Zone	3299-3322
"B" "	3333-3349
"D" "	3354-3365
"E & F" Zone	3370-3378
"G" Zone	3380-3420
"H" "	3431-3447
"I" "	3457-3465
"J" "	3467-3486
"K" "	3496-3512
"L" "	3521-3527
Base Kansas City	3527