

DRILL STEM TEST REPORT

Prepared For: **Vess Oil**

1700 Waterfront Parkway Bld 500
Wichita KS 67206

ATTN: Paul Ramondetta

7 10S 19W Rooks KS

Dunlap #6

Start Date: 2007.03.06 @ 02:01:50

End Date: 2007.03.06 @ 08:59:18

Job Ticket #: 27511 DST #: 1

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Vess Oil

1700 Waterfront Parkway Bld 500
Wichita KS 67206

ATTN: Paul Ramondetta

Dunlap #6

7 10S 19W Roofs KS

Job Ticket: 27511

DST#: 1

Test Start: 2007.03.06 @ 02:01:50

GENERAL INFORMATION:

Formation: **LKC**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 04:10:48

Time Test Ended: 08:59:18

Test Type: **Conventional Bottom Hole**

Tester: **Brian Fairbank**

Unit No: **24**

Interval: **3520.00 ft (KB) To 3688.00 ft (KB) (TVD)**

Total Depth: **3688.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition:

Reference Elevations: **2234.00 ft (KB)**

2230.00 ft (CF)

KB to GR/CF: **4.00 ft**

Serial #: 6769

Inside

Press@RunDepth: **78.38 psig @ 3524.01 ft (KB)**

Start Date: **2007.03.06**

End Date:

2007.03.06

Capacity: **7000.00 psig**

Last Calib.:

2007.03.06

Start Time: **02:01:50**

End Time:

08:59:18

Time On Btm: **2007.03.06 @ 04:10:33**


Time Off Btm: **2007.03.06 @ 07:11:03**

TEST COMMENT: **IFP Weak to good blow 1" - 7"**

ISI No blow back

FFP Weak to good blow 1/2" - 8"

FSI No blow back



PRESSURE SUMMARY

Time (Mn.)	Pressure (psig)	Temp (deg F)	Annotation
0	1736.34	90.88	Initial Hydro-static
1	27.90	90.53	Open To Flow (1)
29	47.64	93.02	Shut-In (1)
76	470.29	94.93	End Shut-In (1)
76	49.66	94.72	Open To Flow (2)
119	78.38	95.84	Shut-In (2)
181	400.59	98.35	End Shut-In (2)
181	1687.07	98.87	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
95.00	WM 15%W 85%M	1.33
14.00	VSOCWM 5%O 40%W 55%M	0.20
1.00	OIL TSTM	0.01

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27511

DST#: 1

ATTN: Paul Ramondetta


Test Start: 2007.03.06 @ 02:01:50

Tool Information

Drill Pipe:	Length: 3529.00 ft	Diameter: 3.80 inches	Volume: 49.50 bbl	Tool Weight: 5000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 30000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose: 80000.00 lb
			<u>Total Volume: 49.50 bbl</u>	Tool Chased 1.00 ft
Drill Pipe Above KB:	29.00 ft			String Weight: Initial 49000.00 lb
Depth to Top Packer:	3520.00 ft			Final 51000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	168.02 ft			
Tool Length:	188.02 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Shut In Tool	5.00			3505.00	
Hydraulic tool	5.00			3510.00	
Packer	5.00			3515.00	20.00 Bottom Of Top Packer
Packer	5.00			3520.00	
Stubb	1.00			3521.00	
Perforations	2.00			3523.00	
Change Over Sub	1.00			3524.00	
Recorder	0.01	6769	Inside	3524.01	
Blank Spacing	155.00			3679.01	
Change Over Sub	1.00			3680.01	
Perforations	5.00			3685.01	
Recorder	0.01	13548	Outside	3685.02	
Bullnose	3.00			3688.02	168.02 Bottom Packers & Anchor

Total Tool Length: 188.02



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27511

DST#: 1

ATTN: Paul Ramondetta

Test Start: 2007.03.06 @ 02:01:50

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

25000 ppm

Viscosity: 51.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.16 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2600.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
95.00	WM 15%W 85%M	1.333
14.00	VSOCWM 5%O 40%W 55%M	0.196
1.00	OIL TSTM	0.014

Total Length: 110.00 ft

Total Volume: 1.543 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: 15' GIP


DST Test Number: 1


7 10S 19W Rocks KS

Vess Oil

Inside

Serial #: 6769





DRILL STEM TEST REPORT

Prepared For: **Vess Oil**

1700 Waterfront Parkway Bld 500
Wichita KS 67206

ATTN: Paul Ramondetta

7 10S 19W Rooks KS

Dunlap #6

Start Date: 2007.03.07 @ 00:19:19


End Date: 2007.03.07 @ 09:05:17

Job Ticket #: 27512 DST #: 2

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Vess Oil

1700 Waterfront Parkway Bld 500
Wichita KS 67206

ATTN: Paul Ramondetta

Dunlap #6

7 10S 19W Rocks KS

Job Ticket: 27512

DST#: 2

Test Start: 2007.03.07 @ 00:19:19

GENERAL INFORMATION:

Formation: **Arbuckle**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 02:18:17

Time Test Ended: 09:05:17

Test Type: Conventional Bottom Hole

Tester: Brian Fairbank

Unit No: 24

Interval: **3709.00 ft (KB) To 3777.00 ft (KB) (TVD)**

Total Depth: 3777.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition:

Reference Elevations: 2234.00 ft (KB)

2230.00 ft (CF)

KB to GR/CF: 4.00 ft

Serial #: 6769

Inside

Press@RunDepth: 725.27 psig @ 3713.01 ft (KB)

Start Date: 2007.03.07

End Date:

2007.03.07

Start Time: 00:19:19

End Time:

09:05:17

Capacity: 7000.00 psig

Last Calib.: 2007.03.07

Time On Btm: 2007.03.07 @ 02:18:02

Time Off Btm: 2007.03.07 @ 05:21:17


TEST COMMENT: IFF BOB 1 min.

ISI Sur blow back died 22 min.

FFP BOB 2 min.

FSI No blow back

Pressure vs. Time



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1818.14	93.79	Initial Hydro-static
1	116.25	93.23	Open To Flow (1)
30	478.46	108.23	Shut-In(1)
76	867.57	106.71	End Shut-In(1)
76	491.26	106.46	Open To Flow (2)
120	725.27	108.81	Shut-In(2)
180	861.87	106.51	End Shut-In(2)
184	1834.98	105.46	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
495.00	MW scum O 95%W 5%M	6.94
185.00	GO & WCM 30%G 15%O 35%W 20%M	2.60
250.00	W & GOCM 25%G 15%O 5%W 55%M	3.51
590.00	W & GHOCM 20%G 30%O 25%W 25%M	8.28
75.00	FREE OIL	1.05

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27512

DST#: 2

ATTN: Paul Ramondetta

Test Start: 2007.03.07 @ 00:19:19


Tool Information

Drill Pipe:	Length: 3693.00 ft	Diameter: 3.80 inches	Volume: 51.80 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose:	110000.0 lb
			Total Volume: 51.80 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	4.00 ft			String Weight: Initial	49000.00 lb
Depth to Top Packer:	3709.00 ft			Final	59000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	68.02 ft				
Tool Length:	88.02 ft				
Number of Packers:	2	Diameter: 6.75 inches			
Tool Comments:					
Tool was plugged					

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
------------------	-------------	------------	----------	------------	----------------

Shut In Tool	5.00			3694.00	
Hydraulic tool	5.00			3699.00	
Packer	5.00			3704.00	20.00 Bottom Of Top Packer
Packer	5.00			3709.00	
Stubb	1.00			3710.00	
Perforations	2.00			3712.00	
Change Over Sub	1.00			3713.00	
Recorder	0.01	6769	Inside	3713.01	
Blank Spacing	31.00			3744.01	
Change Over Sub	1.00			3745.01	
Perforations	29.00			3774.01	
Recorder	0.01	13548	Outside	3774.02	
Bullnose	3.00			3777.02	68.02 Bottom Packers & Anchor

Total Tool Length: 88.02



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27512

DST#: 2

ATTN: Paul Ramondetta

Test Start: 2007.03.07 @ 00:19:19

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

25 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

37000 ppm

Viscosity: 53.00 sec/qt

Cushion Volume:

bbf

Water Loss: 7.57 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2600.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbf
495.00	MW scum O 95%W 5%M	6.944
185.00	GO & WCM 30%G 15%O 35%W 20%M	2.595
250.00	W & GOCM 25%G 15%O 5%W 55%M	3.507
590.00	W & GHOCM 20%G 30%O 25%W 25%M	8.276
75.00	FREE OIL	1.052

Total Length: 1595.00 ft

Total Volume: 22.374 bbf

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time





DRILL STEM TEST REPORT

Prepared For: **Vess Oil**

1700 Waterfront Parkway Bld 500
Wichita KS 67206

ATTN: Paul Ramondetta

7 10S 19W Rooks KS

Dunlap #6

Start Date: 2007.03.06 @ 02:01:50

End Date:

Job Ticket #: 27513

DST #: 3

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

Vess Oil
1700 Waterfront Parkway Bld 500
Wichita KS 67206

ATTN: Paul Ramondetta

Dunlap #6

7 10S 19W Rooks KS

Job Ticket: 27513

DST#: 3

Test Start: 2007.03.06 @ 02:01:50

GENERAL INFORMATION:

Formation: **Arbuckle (2)**

Deviated: No Whipstock: ft (KB)

Time Tool Opened:

Time Test Ended:

Test Type: Conventional Bottom Hole

Tester: Brian Fairbank

Unit No: 24

Interval: **3790.00 ft (KB) To 3800.00 ft (KB) (TVD)**

Total Depth: 3800.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition:

Reference Elevations: 2234.00 ft (KB)

2230.00 ft (CF)

KB to GR/CF: 4.00 ft

Serial #: 6769 Inside

Press@RunDepth: psig @ 3791.01 ft (KB)

Start Date: 2007.03.07

End Date:

2007.03.08

Start Time: 18:36:13

End Time:

01:37:11

Capacity: 7000.00 psig

Last Calib.: 1899.12.30

Time On Btm: 2007.03.07 @ 20:50:56

Time Off Btm: 2007.03.07 @ 23:34:56


TEST COMMENT: IFP Weak blow throughout 1/2" - 1"

ISI No blow back

FFP Weak blow throughout 1" - died off to 1/2"

FSI No blow back

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1948.46	95.76	Initial Hydro-static
165	1765.25	104.28	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27513

DST#: 3

ATTN: Paul Ramondetta


Test Start: 2007.03.06 @ 02:01:50

Tool Information

Drill Pipe:	Length: 3780.00 ft	Diameter: 3.80 inches	Volume: 53.02 bbl	Tool Weight: 5000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose: 85000.00 lb
		Total Volume:	53.02 bbl	Tool Chased 2.00 ft
Drill Pipe Above KB:	17.00 ft			String Weight: Initial 50000.00 lb
Depth to Top Packer:	3790.00 ft			Final 50000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	10.02 ft			
Tool Length:	37.02 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				
TOOL PLUGGED				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Shut In Tool	5.00			3768.00	
Hydraulic tool	5.00			3773.00	
Jars	5.00			3778.00	
Safety Joint	2.00			3780.00	
Packer	5.00			3785.00	27.00 Bottom Of Top Packer
Packer	5.00			3790.00	
Stubb	1.00			3791.00	
Recorder	0.01	6769	Inside	3791.01	
Perforations	2.00			3793.01	
Perforations	4.00			3797.01	
Recorder	0.01	13548	Outside	3797.02	
Bullnose	3.00			3800.02	10.02 Bottom Packers & Anchor

Total Tool Length: 37.02



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

FLUID SUMMARY

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27513

DST#: 3

ATTN: Paul Ramondetta

Test Start: 2007.03.06 @ 02:01:50

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 48.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.35 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2700.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl

Total Length:

ft

Total Volume:

bbl

Num Fluid Samples: 0


Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:





DRILL STEM TEST REPORT

Prepared For: **Vess Oil**

1700 Waterfront Parkway Bld 500
Wichita KS 67206

ATTN: Paul Ramondetta

7 10S 19W Rooks KS

Dunlap #6

Start Date: 2007.03.08 @ 07:02:02


End Date: 2007.03.08 @ 15:06:15

Job Ticket #: 27514 DST #: 4

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Vess Oil
1700 Waterfront Parkway Bld 500
Wichita KS 67206
ATTN: Paul Ramondetta

Dunlap #6
7 10S 19W Rooks KS
Job Ticket: 27514 **DST#: 4**
Test Start: 2007.03.08 @ 07:02:02

GENERAL INFORMATION:

Formation: **Arbuckle (3)**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 09:26:00
Time Test Ended: 15:06:15

Test Type: Conventional Bottom Hole
Tester: Brian Fairbank
Unit No: 24

Interval: **3790.00 ft (KB) To 3800.00 ft (KB) (TVD)**
Total Depth: 3800.00 ft (KB) (TVD)
Hole Diameter: 7.88 inches Hole Condition:

Reference Elevations: 2234.00 ft (KB)
2230.00 ft (CF)
KB to GR/CF: 4.00 ft


Serial #: 6769

Inside

Press@RunDepth: 569.78 psig @ 3791.01 ft (KB)
Start Date: 2007.03.08 End Date: 2007.03.08
Start Time: 07:02:02 End Time: 15:06:15

Capacity: 7000.00 psig
Last Calib.: 2007.03.08
Time On Btm: 2007.03.08 @ 09:25:45
Time Off Btm: 2007.03.08 @ 12:26:00

TEST COMMENT: IFP BOB 3 min.
ISI Weak sur blow back
FFP BOB 5 min.
FSI Weak sur blow back



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1681.44	91.10	Initial Hydro-static
1	48.78	92.09	Open To Flow (1)
28	301.00	111.40	Shut-In (1)
75	953.15	108.82	End Shut-In (1)
76	304.85	108.86	Open To Flow (2)
118	569.78	111.12	Shut-In (2)
181	935.74	109.73	End Shut-In (2)
181	1790.61	109.99	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
1120.00	MV 5%M 95%W	15.71
95.00	MV scum O 25%M 75%W	1.33

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27514

DST#: 4

ATTN: Paul Ramondetta

Test Start: 2007.03.08 @ 07:02:02


Tool Information

Drill Pipe:	Length: 3780.00 ft	Diameter: 3.80 inches	Volume: 53.02 bbl	Tool Weight: 2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose: 75000.00 lb
		Total Volume: 53.02 bbl		Tool Chased 1.00 ft
Drill Pipe Above KB:	17.00 ft			String Weight: Initial 50000.00 lb
Depth to Top Packer:	3790.00 ft			Final 55000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	10.02 ft			
Tool Length:	37.02 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Shut In Tool	5.00			3768.00	
Hydraulic tool	5.00			3773.00	
Jars	5.00			3778.00	
Safety Joint	2.00			3780.00	
Packer	5.00			3785.00	27.00 Bottom Of Top Packer
Packer	5.00			3790.00	
Stubb	1.00			3791.00	
Recorder	0.01	6769	Inside	3791.01	
Perforations	6.00			3797.01	
Recorder	0.01	13548	Outside	3797.02	
Bullnose	3.00			3800.02	10.02 Bottom Packers & Anchor

Total Tool Length: 37.02



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

FLUID SUMMARY

Vess Oil

Dunlap #6

1700 Waterfront Parkway Bld 500
Wichita KS 67206

7 10S 19W Rooks KS

Job Ticket: 27514

DST#: 4

ATTN: Paul Ramondetta

Test Start: 2007.03.08 @ 07:02:02

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 48.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.35 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2700.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
1120.00	MW 5%M 95%W	15.711
95.00	MW scum O 25%M 75%W	1.333

Total Length: 1215.00 ft

Total Volume: 17.044 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

