

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

15-163-00344

COMPANY AYLWARD DRILLING CO., et al

SEC. 1 T. 10 R. 19W

FARM Mayhew

NO. 1

LOC. NE NE SW

TOTAL DEPTH 3746

COMM. 3-14-51

COMP. 3-26-51


SHOT OR TREATED

CONTRACTOR Aylward Drilling Co.

ISSUED 4-28-51

COUNTY Rooks

KANSAS



CASING

8 5/8" 186' cem. w/100 sx

ELEVATION 2188 DF

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & sand	135	DST: 3577-89 open 20 min.
shale	470	Weak blow for 5 min. Rec.
shale & shells	790	5' of mud. Sl. Oil cut.
red bed	850	
red bed & shale	950	
shale & shells	1050	
sandy shale	1150	
shale & shells	1340	
shale	1565	
lime	1605	
shale & shells	1970	
shale	2107	
shale & lime	2485	
shale	2550	
lime & shale	2690	
shale	2700	
shale & lime	2760	
lime	2840	
shale & lime	3160	
shale	3173	
lime	3305	
lime & shale	3385	
lime	3615	
conglomerate	3685	
lime & shale	3745	
conglomerate	3746	
Total Depth		

Tops:

Anhydrite	1565
Topeka	3154
Heebner	3370
Brown Lime	3394
Lansing-Kansas City	3412
Marmaton	3630
Cherty Conglomerate	3719

3450-52 & 3456-58 Limestone
 Lt. Gry. Fi. Xln. Sl. Tr. of
 leached porosity & Staining.
 No free oil or odor. 3495-98
 & 3501-08 Limestone white Fi.
 Xln. Ls. Fair leached porosity.
 Fair stain. Show free oil in
 samples. DST: 3494-3509 Open
 30 min. Med. blow. Rec. 350
 salt wtr.
 3536-45 Limestone Lt. Gry. Xln.
 Sl. porosity. No stain or odor.
 3577-83 Limestone. Oolitic
 & leached porosity. Fair stain
 & odor. Free oil in samples.