

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


15-163-00991

Company- STRATA DRILLING, INC
Farm- Sparks No. 1

SEC. 3 T. 10 R. 19W
NW SE NW

Total Depth. 3730
Comm. 6-24-56 Comp. 7-3-56
Shot or Treated.
Contractor. Strata Drlg Co., Inc.
Issued. 8-11-56

County Rocks
KANSAS



CASING:
8 5/8" 207' cem w/140 sx

Elevation. 2170 DF

Production. Dry

surface soil	199
shale	520
shell, shale	1070
sand Dakota	1275
shale, shell	1555
anhydrite	1570
shale	1880
shale, lime	2670
shale	2955
shale, lime	3407
lime	3435
lime, shale	3520
lime	3555
shale, lime	3585
lime	3623
lime, Congl.	3650
shale, lime	3680
lime, congl.	3725
lime	3730
Total Depth	

Figures indicate Bottom of Formations.

Tops:
Topeka 3116
Heebner 3326
Tornot 3347
Lansing 3366
Arbuckle 3683

DST #1: 3358-3462, Open
1 hr., shut in 20 min.,
Rec. 1965' salt wtr. BHP 1195#.

DST #2: 3566-3590, Open
30 min, shut in 20 min. Rec.
35' mud. BHP 65#.

DST #3: 3591-3628, Open
30 min., shut in 20 min.
Recovered 50' mud., BHP 760#.