

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-103-00423

Company- L. B. STABLEFORD
Farm- Sutor No. 1

SEC. 5 T. 10 R. 19W
SE SW SE

Total Depth. 3769
Comm. 4-15-52 Comp. 4-29-52
Shot or Traced.
Contractor. K & E Drlg Co.
Issued. 7-5-52

County Rocks
KANSAS



Elevation. 2227 RB
2224 (m)
Production. 80 bbls, no water

CASING:

8 5/8" 171' cem w/135 sx
5 1/2" 3762' cem w/125 sx ✓

Figures indicate Bottom of Formations.

sand	130
shale blue	225
shale, shells	450
shale, clay	775
sand	805
sand, shale	960
sand, shells, shale	1060
sand	1100
red bed, shale	1586
shale, shells	1630
anhydrite	1670
shale, lime	2803
lime	2870
lime, shale	3255
lime	3338
lime, shale	3389
lime	3466
lime, shale	3500
lime	3522
lime (cherty)	3555
lime-strks of chert	3592
lime	3690
lime- cherty	3724
lime	3766
lime	3769
Total Depth	

Tops: Scout,	
Heebner	3415
Lansing	3452
Conglomerate	3682
Arbuckle	3760