

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-01896

Company- NADEL & GUSSMAN OIL CO.

Farm- Gish

No. 3

SEC. 6

T. 10

R. 19W

NW SW SW

Total Depth. 3757

Comm. 2-1-52

Comp. 2-12-52


Shot or Treated.

Contractor.

Issued. 3-22-52

County Rocks

KANSAS



CASING:

8 5/8" 165' cem. w/115 sx.

5 1/2" 3754' cem. w/150 sx.

Elevation. 2238 R.B.

2235(m)

Production. 3000 bbls. &
no wtr.

Figures indicate Bottom of Formations.

clay, sand, & shale	168
shale	595
shale, shells & sand	1422
sand, redbed & shale	1650
anhyd.	1690
shale & shells	1845
lime brkn & shale	2175
lime bkn	2425
lime & shale	3500
lime	3712
congl. cherty	3744
shale	3753 $\frac{1}{2}$
arb.	3757
Total Depth	

Tops:

Heebner	3425
Lansing-K.C.	3465
congl.	3703
Simpson	3742
arb.	3753 $\frac{1}{2}$

DP FH 1000' oil /1 hr.

Sw. 55 BOPH 1000' OB

Pot. 7510