

Geological Survey

WICHITA BRANCH KANSAS DRILLERS LOG

API No. 15 ————— County ————— Number —————

Operator

John P. Jennings Oil Co.

Address

200 E. First, Suite 309, Wichita, KS 67202

Well No.

5

Lease Name

BALDWIN

Footage Location

660 feet from (N) ~~XX~~ line 330 feet from (E) ~~XX~~ line

Principal Contractor

John O. Farmer, Inc.

Geologist

Richard E. Roby

Spud Date

11-21-77

Total Depth

3780

P.B.T.D.

Date Completed

11-30-77

Oil Purchaser


None -- D & A

S. 9 T. 10S R. 19W ^E_W

Loc. C E/2 NE NW

County ————— Rocks

640 Acres



Locate well correctly

Elev.: Gr. 2210

DF 2213 KB 2215

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8-5/8	26	202	Common	140	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator John P. Jennings Oil Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 5	Lease Name BALDWIN		Dry Hole
S 9 T10S R 19WE W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
Sand & Shale	0	202	Sample Tops:
Shale	202	780	Anhydrite 1598 +617
Shale & Sand	780	1075	Topeka 3202 -987
Sand	1075	1275	Heebner Shale 3413 -1198
Shale & Shells	1275	1320	Lansing-K.C. 3451 -1236
Shale, Shells & Sand	1320	1598	Base Kansas City 3657 -1442
Anhydrite	1598	1634	Penn. Conglomerate 3715 -1500
Shale & Shells	1634	2050	Arbuckle 3774 -1559
Shale & Lime	2050	2535	Total Depth 3780 -1565
Lime & Shale	2535	2835	
Shale & Lime	2835	3275	
Lime & Shale	3275	3530	
Lime	3530	3678	
Lime & Shale	3678	3715	
Chert & Congl.	3715	3755	
Cong. Chert	3755	3780	
DST# 1 3480' - 3507' 5' mud, open 30, shut 30, open 30, shut 30 all pressures 20# DST# 2 3512' - 3545' 15' mud open 30, shut 30, open 30, shut 30 IFP 20, FFP 20 ISP 459, FSI 448 DST# 3 3600' - 3633' recovered 15' mud open 30, shut 30, open 30, shut 30 ISP 30 30 FFP 30 30 ISP 438 FSI 438			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received 12-6-77	John P. Jennings Signature Operator Title 12-6-77 Date		

0462L