

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-62395


Company- C. U. BAY
Farm- W. Gick

No. 1

SEC. 12 T. 10 R. 19W
SW NW SW

Total Depth. 3647
Comm. 2-23-54 Comp. 3-6-54
Shot or Treated.
Contractor. Lewis Drlg. Co.
Issued. 3-27-54

County Rooks KANSAS



CASING:

8 5/8" 152'

Elevation. 2120

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	880
shells	950
sand & shale	1150
shale & shells	1490
anhydrite	1530
shale & lime	2650
lime broken	2755
lime & shale	3065
lime	3110
lime & shale	3183
lime	3421
lime & shale	3458
lime	3535
conglomerate	3595
lime	3647
Total Depth	

Tops:	
Heebner	3280
Toronto	3300
Mansing	3319
Conglomerate	3553
Arbuckle	3640

DST: 3286-3312 open 1 hr.
rec. 10' mud. 90# BHP.
DST: 3343-3388' open 1 hr.
rec. 25' SOCM 0 BHP.
DST: 3386-3419' open 1 hr.
35' OCM 180# BHP
DST: 3464-3505' 1 1/2 hr. 25'
thin wtry mud 280# BHP
DST: 3640-45' open 1 hr.
12' mud w/few specks blk
heavy oil. 240# BHP.