


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company SINCLAIR PRAIRIE OIL CO.
Farm H. J. Vohs No. 5

SEC. 13 T. 10 R. 19 W
NW SE NW
990' fs & EL N $\frac{1}{4}$

Total Depth. 3601' PB 3414 $\frac{1}{2}$ '
Comm. 8-22-46 Comp. 9-7-46
Shot or Treated.
Contractor. Harbar Drlg. Co.
Issued. 11-2-46

County. Rocks
KANSAS



CASING:

9 5/8" 1475' Cem. DFM
7" 3597' Cem.

Elevation. 2093

Production. Pot. 1233 BO, no wtr.

Figures Indicate Bottom of Formations.

sand-rock-clay	50
sand	70
shale & sand	120
shale & shells	300
shale	460
shale & shells	705
shale	880
lime	900
sand	1145
shale & shells	1365
red bed	1460
anhydrite	1477
lime & shale	2030
shale	2070
lime & shale	2270
lime	2490
shale & lime	2615
lime	2745
lime & shale	2885
shale	3000
shale & shells	3035
lime	3100
lime sft	3190
lime	3565
shale	3601

Total Depth PB 3414 $\frac{1}{2}$

Tops:	DF	Sur. Level
Lansing KC	3289	3286
Arbuckle	3597	3594

Acid 1000 gal. swab 10 BOPH, no wtr.

Set plug 3414 $\frac{1}{2}$ ' Perf. 18 holes
3320-25' acid 1000 gals.

Swbd 40 BOPH, no wtr.

9-20-46 State Pot. 1233 BO, no wtr. (Pmpd 410.95 oil in 8 hr.)

Top cement plug @ 3560' not drld.
Perf. 9 shots 3477-80' acid 1500
gal. made 2 BO, 6 BOPH
Set plug 3466' Perf. 23 holes
3448-58'