

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E Murdock Wichita, Kansas

15-103-90380


Company - SINCLAIR OIL AND GAS CO
Farm - Vohs No. 8

SEC. 13 T. 10 R. 19W
SW SW NW
330' fr s+h & WL NW $\frac{1}{4}$

Total Depth. 3799
Comm. 12-28-49 Comp. 2-1-50
Shot or Treated.
Contractor. Holm Louis Drilling
Issued. 2-18-50

County. Rocks

KANSAS



Elevation. _____

Production. SMDW

CASING:
10 3/4" 188' comw/ 150 sxs
7" 3671' comw/ 500 sxs
Figures Indicate Bottom of Formations.

sand & shale	200
shale and shells	396
shale and sand	926
sand	1171
shale and shells	1411
anhydrite	1456
red bed	1556
shalells and shale	1971
lime	2001
lime and shale	2351
lime	2431
shale and lime shells	2496
lime and shale	2671
shale and lime	2796
shale	2804
lime and shale	2986
lime	3031
lime and shale	3111
lime	3308
lime and shale	3331
lime R.T.D.	3686
lime	3799
Total Depth	

TOPS:

KansCity	3260
Arbuckle	3571

Drill stem test 3258-83' open 45 mins
recovered 177' oil cut mud.
Temp. survey showed top cmt 1875'
Perforated 6 holes in 7" 454-456'
Cemented w/200 sx Temp survey showed
top cmt at 456'
Drilled cement, cleaned out to btn.
Took 300 bbl wtr on vacuum in 30 mins.
Completed for a disposal well.

Ran Schlumberger at 3686'

Corrected to surface level measure.