

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

15-163-01954

Company - SKELLY OIL CO.

Farm - L. Scoggins

No. 5

SEC. 18 T. 10 R. 19W


S. 1/2 NW SW

990' fr NL 330' fr ML of

S. 1/2

County. Rooks

KANSAS



Total Depth. 3777

Comr. 5-29-49

Comp. 6-23-49

Shot or Treater. Shot

Contractor. Herndon Drlg. Co.

Issued. 10-22-49

CASING:

8 5/8" 1635' con. w/650 sx.

5 1/2" 3773' con. w/200 sx.

Elevation. 2231 Ind

Production. S.C.C. pot. 3000 bbls.

Figures Indicate Bottom of Formations.

surface soil, sand
 & shells 500
 shells & sand rock 1625
 anhyd. 1635
 reamed 9 7/8" hole to 12 1/4"
 anhyd. 1670
 shale & shells 2205
 shale & lime 2655
 shale & shells 2910
 lime & shale 3335
 lime 3725
 lime shells & shale 3772
 dolo. gry & brn fine
 to med. xyl. 3775
 dolo. coarsely xyl. 3777
 Total Depth

Tops:
 Anhyd. 1625
 Heebner 3424
 Toronto lime 3442
 Lansing lime 3462
 Congl. 3686
 Simpson shale 3758
 Arbuckle lime 3772

3493-3585 fair por. & sat.
 3772'-3775 fair por. & sat.
 3775-3777 good por. & sat.

Acid treatment:

6-24-49 500 quts. shot between

3773-3777 By Dowell

Producing Formation: Arbuckle 3773-3777

1400' OIH I.P. before acid.

I. P. after acid: POB 9 hrs. for Ind.

Pod. 3352 bbls. to estab. 24 hrs. SCC
 pot of 3000 bbls. (Max)