

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

15-163-01960


Company - THE TEXAS COMPANY
Farm - H. Berland No. 5

SEC. 19 T. 10 R. 19W
SW SE NW

Total Depth. 3796½'
Comm. 9-6-48 Comp. 9-30-48
Shot or Treated. Acidized
Contractor. Stickel Drlg. Co.
Issued. 11-20-48

County. Rooks

KANSAS



Elevation. 2226.2nd

Production. Pmp. 265.26 BO, 10 BW

CASING:

8-5/8" 1621' Cem. #/800 Sx.
5-1/2" 3792' Cem. #/100 Sx.

Figures Indicate Bottom of Formations.

clay & sand	100
shale & gravel	200
shale	300
shale & shells	735
shale & sand	960
sand	1040
shale & shells	1396
red bed	1500
shale	1575
shale & shells	1612
anhydrite	1640
shale	1650
shale sdy	1680
red bed & shale	1780
shale	1900
salt	2000
shale & lime	2070
shale & shells	2165
shale & lime	2300
lime brkn	2350
shale brwn & lime	2380
lime	2465
lime & shale	2540
lime	2690
lime & shale	2725
lime	2965
shale & lime	3110
lime	3452
lime chert	3492
lime	3765
conglomerate	3796½
Total Depth	

Tops:

Topoka	3229
Heebner	3440
Lansing	3477
Conglomerate	3715
Simpson	3769
Arbuckle	3791

- 9-26-48 Bailed hole, drilled plug shut down 4 hrs, hole filled up 550' oil, no wtr - swabbed down & swabbed 5 hrs, swabbed 2½ BO no water per hr.
- 9-27-48 Acidized w/500 gals. took acid at 350% press. swabbed 44.59 BO, no wtr in 10 hrs.
- 9-28-48 Swabbed hole down (30 BO) swabbed 5 BO, no wtr Per hr 6 hrs.
- 9-29-48 Acid. w/500 gals, 15%, down casg. well took acid on vacuum - swabbed back load & swabbed 67 BO in 14 hours.
- 9-30-48 Deepened well 1½' & swabbed well 9 hrs - swabbed 4.14 BO, no water per hour.