

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

15-163-01973


Company - THE TEXAS COMPANY
Farm - H. Berland "A" No. 10

SEC. 19 T. 10 R. 19W
SW SW NW

Total Depth. 3787
Comm. 12-29-48 Comp. 1-18-49
Shot or Treated. Acidized
Contractor. Stickle Drlg.
Issued. 2-12-49

County. Rooks

KANSAS



Elevation. 2227 ft.

Production. Pumping 211 BO, 1 1/2 BW

CASING:

8 5/8" 1623' cem w/800 sx.
5 1/2" 3785' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay, sand 35
sand, gravel 100
shale, sand 250
shale, shells 300
shale, iron 330
shale, shells 540
shale, shells, sand 825
shale, shells 935
shale, sand, shells 1000
shale, shells 1035
sand, shale, shells 1100
sand, shale 1305
sand 1335
shale, shells, sand 1465
shale, red, shells 1613
anhydrite 1665
shale, shells 1980
salt 2060
salt, shale 2105
shale, shells 2280
shale, lime 2620
lime brkn 2720
lime, shale 3280
lime 3720
conglomerate 3785
lime 3787
total depth

Tops:

Anhydrite 1613
Heebner 3138
Lansing 3476
Conglomerate 3720
Simpson 3755
Arbuckle 3784

REMARKS:

1-16-49, cleaned out to bottom, tested 10 gal oil pr hr, acidized w/500 gal max press 550#, treated at 500#, pressure dropped after treatment 300# in 3 mins.

1-17-49 swbbed down tested 10 gal oil pr hr for 4 hrs, oil broke in and filled up 1000' in 1 hr, swbd 85 bbl oil in 17 hrs.

1-18-49, ran tubing and acid w/500 gal, max press 900#, pressure drop of 200# in 2 minutes after acid.

2-10-49, took completion test: Pumped 211 1 1/2 BW in 24 hrs.