

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock, Wichita, Kansas


15-163-0144

Company - THE TEXAS COMPANY
 Farm - H. Berland "A" No. 15

SEC. 19 T. 10 R. 19W
 NW NW NW

Total Depth. 3766
 Comm. 8-11-49 Comp. 8-24-49
 Shot or Treated.
 Contractor. Stickle Drlg.
 Issued. 9-24-49

County. Rocks
 KANSAS



Elevation. 2217(m)
 2219 RB (end)

Production. Draw Down 3058 bbls.
 oil, no water

Figures Indicate Bottom of Formations.

clay	30
sand	105
shale	250
shale, shells	480
gravel	580
shale, red bed	600
shale	865
shale, shells	1585
shale	1609
anhydrite	1650
red bed	1800
shale, shells	1940
lime, shale	2495
lime	2895
lime, shale	3275
lime	3741
lime, chert	3766
Total depth	

Tops:
 Anhydrite 1609
 Heebner 3421
 Lansing 3457
 Conglomerate 3694
 Simpson 3730
 Arbuckle 3761

REMARKS:

8-30-49, Drilled cement, filled up 1900'
 including 1000' water load (900' oil)
 8-31-49, Swbd well for 4 hrs, 500' off bottom,
 swbd 33 bbls oil, no wtr pr hr. Cleared out to
 bottom, swbd for 7 hrs 500' off bottom;
 1st hr, 33 bbls. oil
 2nd hr, 46 bbls oil
 3rd hr, 46 bbls oil
 4th hr, 46 bbls oil
 5th hr, 25 bbls oil
 6th hr, 32 bbls oil
 7th hr, 50 bbls oil.

9-2-49, State draw down pot. 3058 bbls,
 of oil, no water pr day.