

KANSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas
APR 19 1969

15-163-20167

20-10-MW

B E E L A N D # 1

REX & MORRIS, ETAL

Elevation: 2205 RB
2200 GL

TOTAL DEPTH: 3776' RB
CONTRACTOR: GABBERT-JONES, INC.
COMMENCED: 12-29-68
COMPLETED: 1-18-69
INITIAL PROD.: 12 BOFH

Location: NE SE NW
Section 20-108-19W
Rooks County, Kansas

Casing Record:
8 5/8" OD Set at 205' RB
W/147 Sacks Cement
5 1/2" OD Set at 3765' RB
W/75 Sacks Cement
Perforated at 1618' RB &
Cemented W/350 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	205'
Shale	267'
Shale W/sand	1055'
Sand	1300'
Shale & Red Bed	1577'
Anhydrite	1620'
Shale	1840'
Shale & Lime	2060'
Salt Section	2690'
Shale & Lime	3220'
Shale	3295'
Lime	3467'
Lime & Shale	3525'
Lime	3710'
Lime & Shale	3763'
Arbuckle Dolomite R.T.D.	3776'

NO CARD

R.U.C.T., DRILLED CEMENT, CLEANED OUT TO T.D.
HOLE FILLED 500' IN 2 HRS. MOORED, 1500' FILL UP
IN 14 HRS. SWAB DOWN 35 HRS. OIL, NO WATER.
ACIDIZED W/300 GAL 38% ACID. 1700' FILL UP
IN 14 HRS. SWAB TEST 36 HRS. OIL IN 3 HRS.
NO WATER. SET BRIDGE PLUG AT 3720', PERFORATED
& SHOTS AT 1618', CEMENTED CASING W/350 SACKS
CEMENT & 6% GEL. CEMENT CIRCULATED. DRILLED CEMENT.
CLEANED HOLE TO T.D. P.O.P.