

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk. Bldg., Wichita, Kansas

15-103-03377


Company - THE TEXAS COMPANY  
 Farm - H. Berland "B" No. 1

SEC. 30 T. 10 R. 19W  
 NE NE NW

Total Depth. 3815'  
 Comm. 7-27-48 Comp. 8-17-48 ✓  
 Shot or Treated.  
 Contractor. Stickle Drlg. Co.  
 Issued. 10-30-48

County. Rooks

KANSAS



Elevation. 2239 Ind.  
 Pumping  
 Production. 421 BO, 17 B wtr.

CASING:

8 5/8" 1631' cem w/800 sx.  
 5 1/2" 3811' cem w/75 sx.

Figures Indicate Bottom of Formations.

surface clay	45
sand	100
sand and gravel	190
shale	395
shale and shells	1350
shale	1550
red bed	1619
anhydrite	1650
red rock	1750
shale	1870
shale and shells	1970
salt and shale	2155
shale and shells	2265
lime and shale	2415
lime brkn	2470
shale brn. & lime	2515
lime	2700
shale sdy & lime	2730
lime	2950
shale, lime shells	3000
lime and shale	3060
lime brkn	3110
lime	3225
shale	3240
lime	3809
conglomerate	3815
total depth	

Tops:

Topeka	3238
Hoebner	3450
Lansing	3491
Conglomerate	3740
Simpson	3770
Arbuckle	3810

Remarks

8-16-48, Drilled cement,  
 had 650' fill-up first hr.  
 Cleaned out to bottom,  
 swbd 172 BO, no wtr 6 hrs.  
 8-17-48, swabbed 12 BOPH  
 for 4 hrs.