

P1

KANSAS
State Geological Survey
WELL COMPLETION REPORT AND DRILLER'S LOG
WICHITA BRANCH

API No. 15 — 163 — 20,904
 County Number

Operator
R. P. Nixon Operations

Address
207 West 12th St. Hays, Kansas 67601

Well No. #1 Lease Name
 Keller

Footage Location
330 feet from (N) (SX) line 990 feet from (E) (W) line of NW $\frac{1}{4}$

Principal Contractor Geologist
DREILING OIL COMPANY DAN A NIXON


Spud Date Date Completed Total Depth P.B.T.D.
4-6-79 4-11-79 3765

Directional Deviation Oil and/or Gas Purchaser
 CLEAR CREEK INC

S. 31 T. 10 R. 19 W

Loc. NW NE NW

County Rooks



Locate well correctly
 Elev.: Gr. 2203

DF 2205 KB 2208

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 $\frac{1}{4}$	8 5/8	28#	253	COMMON	150	8 sx quickset
PRODUCTION	7 7/8	4 $\frac{1}{2}$ "	9.5#	3764	COMMON	125	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type D.P.	Depth interval
			TWO		3720-30
			TWO	D.P.	3505-08
Size 2"	Setting depth 3762	Packer set at -----			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 GALS ACID	3720-30
1000 GALS 28% ACID	3505-08

INITIAL PRODUCTION

Date of first production <u>5-15-79</u>	Producing method (flowing, pumping, gas lift, etc.) <u>PUMPING</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>15</u> bbls. Gas <u>45</u> bbls. Water <u>45</u> bbls. Gas-oil ratio <u>CFPB</u>
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator R P NIXON OPERATIONS		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL	
Well No. ONE	Lease Name KELLER		
S <u>31</u> T <u>10</u> R <u>19</u> ^{XE} _W ROOKS COUNTY KANSAS			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
ANHYDRITE (DRLRS)	1612		
TOPEKA LIME	3203		
HEEBNER SHALE	3409		
TORONTO LIME	3433		
LANSING-KANSAS CITY	3450		
BASE OF KANSAS CITY	3674		
BASAL PENNSYLVANIAN CONGLOMERATE	3698		
CONGLOMERATE SAND	3619		
ARBUCKLE DOLOMITE	3752		
R T D	3765		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 _____ Signature SECRETARY _____ Title 6-26-81 _____ Date		

6193L

31-10-19W

State Geological Survey DREILING OIL, INC.

VICTORIA, KANSAS

Victoria, Kansas 67671

15163-20904

MAY 8 0 REC'D

R. P. Nixon Oil Operations **WELL LOG**
207 West 12

Company Hays, KS 67601

Sec. 31 Twp. 10 Rng. 19

Farm Keller No. 1

Location NW NE NW

Total Depth 3,765

County Rooks

Comm. 4-5-79 Comp. 4-12-79

Elevation: 2210 K. B.

Contractor Dreiling Oil, Inc.
Victoria, KS 67671

2207 D. F.

2205 G. R.

Casing Record

Cement Record

Production:

253' - 8 5/8"
3,764' - 5 1/2"

150 sacks cement
cemented w/125 sacks common

Figures Indicate Bottom of Formations

0'	180'	Top Soil-Sand
180'	258'	Shale
258'	958'	Sand & Shale
958'	1090'	Shale
1090'	1305'	Sand
1305'	1612'	Shale & Red Bed
1612'	1653'	Anhydrite
1653'	2258'	Shale
2258'	2850'	Shale & Lime
2850'	3110'	Shale
3110'	3337'	Lime & Shale
3337'	3765'	Lime
3765'	T.D.	

STATE OF KANSAS)

)ss

COUNTY OF ELLIS)

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1979

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc.
upon oath states that the above and foregoing is a true and correct
copy from the Daily Drilling Report from the Keller #1.


JOSEPH A. HESS

Subscribed and sworn to before me this 20th day of April, 1979