

TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Poverty Oil LLC**

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

19 10 20 Rooks KS

Romine #3-19

Start Date: 2007.06.05 @ 18:21:37

End Date: 2007.06.05 @ 23:27:07

Job Ticket #: 28333


DST #: 1

15-163-23614
NW SESESE
480 FSL 580 FEL

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Poverty Oil LLC

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

Romine #3-19

19 10 20 Rooks KS

Job Ticket: 28333

DST#: 1

Test Start: 2007.06.05 @ 18:21:37

GENERAL INFORMATION:

Formation: **Topeka**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 20:17:52

Time Test Ended: 23:27:07

Interval: **3158.00 ft (KB) To 3178.00 ft (KB) (TVD)**

Total Depth: **3178.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition: **Good**

Test Type: **Conventional Bottom Hole**

Tester: **Tyson Flax**

Unit No: **21**

Reference Elevations: **2120.00 ft (KB)**

2115.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 8320 **Inside**

Press@RunDepth: **20.92 psig @ 3159.00 ft (KB)**

Start Date: **2007.06.05**

End Date: **2007.06.05**

Capacity: **7000.00 psig**

Last Calib.: **2007.06.05**


Start Time: **18:21:39**

End Time: **23:27:07**

Time On Btm: **2007.06.05 @ 20:17:37**

Time Off Btm: **2007.06.05 @ 21:53:22**

TEST COMMENT: IFP Weak surface blow throughout
ISI No blow back
FFP No blow flushed tool weak surface blow died in 1 min
FSI No blow back



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1459.28	98.48	Initial Hydro-static
1	11.41	97.94	Open To Flow (1)
18	13.08	98.35	Shut-In (1)
46	886.15	98.73	End Shut-In (1)
50	16.39	99.03	Open To Flow (2)
68	20.92	99.04	Shut-In (2)
96	831.65	99.61	End Shut-In (2)
96	1405.79	99.85	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
5.00	Mud w/ scum of Oil	0.07

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28333

DST#: 1

ATTN: Ed Glassman

Test Start: 2007.06.05 @ 18:21:37

Tool Information

Drill Pipe:	Length: 3155.00 ft	Diameter: 3.82 inches	Volume: 44.72 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	40000.00 lb
			Total Volume: 44.72 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	18.00 ft			String Weight: Initial	32000.00 lb
Depth to Top Packer:	3158.00 ft			Final	32000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	20.00 ft				
Tool Length:	41.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		
Tool Comments:					

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3138.00	
Shut In Tool	5.00			3143.00	
Hydraulic tool	5.00			3148.00	
Packer	5.00			3153.00	21.00 Bottom Of Top Packer
Packer	5.00			3158.00	
Stubb	1.00			3159.00	
Recorder	0.00	8320	Inside	3159.00	
Perforations	16.00			3175.00	
Recorder	0.00	13401	Inside	3175.00	
Bullnose	3.00			3178.00	20.00 Bottom Packers & Anchor
Total Tool Length:	41.00				



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28333

DST#: 1

ATTN: Ed Glassman

Test Start: 2007.06.05 @ 18:21:37

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 47.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.98 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 1300.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
5.00	Mud w / scum of Oil	0.071

Total Length: 5.00 ft

Total Volume: 0.071 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time





DRILL STEM TEST REPORT

Prepared For: **Poverty Oil LLC**

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

19 10 20 Rooks KS

Romine #3-19

Start Date: 2007.06.07 @ 05:17:12

End Date: 2007.06.07 @ 11:16:57

Job Ticket #: 28334

DST #: 2

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620

Poverty Oil LLC

Romine #3-19

19 10 20 Rooks KS

DST # 2

LKC "H-K"

2007.06.07



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Poverty Oil LLC

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

Romine #3-19

19 10 20 Rooks KS

Job Ticket: 28334

DST#: 2

Test Start: 2007.06.07 @ 05:17:12

GENERAL INFORMATION:

Formation: LKC "H-K"

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 06:43:27

Time Test Ended: 11:16:57

Test Type: Conventional Bottom Hole

Tester: Tyson Flax

Unit No: 21

Interval: 3504.00 ft (KB) To 3605.00 ft (KB) (TVD)

Total Depth: 3605.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2120.00 ft (KB)

2115.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 8320

Inside

Press@RunDepth: 160.84 psig @ 3511.00 ft (KB)

Start Date: 2007.06.07

End Date:

2007.06.07

Capacity: 7000.00 psig

Last Calib.: 2007.06.07

Start Time: 05:17:14


End Time:

11:16:57

Time On Btm: 2007.06.07 @ 06:43:12

Time Off Btm: 2007.06.07 @ 09:12:12

TEST COMMENT: IFP BOB in 10 min
ISI No blow back
FFP BOB in 17 min
FSI No blow back



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1710.95	100.79	Initial Hydro-static
1	29.53	100.33	Open To Flow (1)
15	61.70	100.60	Shut-In (1)
59	1037.96	104.56	End Shut-In (1)
60	83.66	104.41	Open To Flow (2)
105	160.84	106.22	Shut-In (2)
149	944.91	109.97	End Shut-In (2)
149	1647.76	110.28	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
120.00	MW 90%W 10%M	1.70
120.00	WM 40%W 60%M	1.70
80.00	VSOCWM 2%O 8%W 90%M	1.13

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28334

DST#: 2

ATTN: Ed Glassman

Test Start: 2007.06.07 @ 05:17:12


Tool Information

Drill Pipe:	Length: 3502.00 ft	Diameter: 3.82 inches	Volume: 49.64 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	50000.00 lb
		Total Volume:	49.64 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	19.00 ft			String Weight: Initial	35000.00 lb
Depth to Top Packer:	3504.00 ft			Final	39000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	101.00 ft				
Tool Length:	122.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3484.00	
Shut In Tool	5.00			3489.00	
Hydraulic tool	5.00			3494.00	
Packer	5.00			3499.00	21.00 Bottom Of Top Packer
Packer	5.00			3504.00	
Stubb	1.00			3505.00	
Perforations	5.00			3510.00	
Change Over Sub	1.00			3511.00	
Recorder	0.00	8320	Inside	3511.00	
Blank Spacing	64.00			3575.00	
Change Over Sub	1.00			3576.00	
Perforations	26.00			3602.00	
Recorder	0.00	13401	Inside	3602.00	
Bullnose	3.00			3605.00	101.00 Bottom Packers & Anchor

Total Tool Length: 122.00



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28334

DST#: 2

ATTN: Ed Glassman

Test Start: 2007.06.07 @ 05:17:12

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

55000 ppm

Viscosity: 45.00 sec/qt

Cushion Volume:

bbl

Water Loss: 9.39 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2300.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
120.00	MW 90%W 10%M	1.701
120.00	WM 40%W 60%M	1.701
80.00	VSOCWM 2%O 8%W 90%M	1.134

Total Length: 320.00 ft

Total Volume: 4.536 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time





TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Poverty Oil LLC**

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

19 10 20 Rooks KS

Romine #3-19

Start Date: 2007.06.07 @ 20:13:10

End Date: 2007.06.08 @ 03:08:40

Job Ticket #: 28335 DST #: 3

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Poverty Oil LLC

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

Romine #3-19

19 10 20 Rooks KS

Job Ticket: 28335

DST#: 3

Test Start: 2007.06.07 @ 20:13:10

GENERAL INFORMATION:

Formation: **Arbuckle**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 22:30:40

Time Test Ended: 03:08:40

Test Type: **Conventional Bottom Hole**

Tester: **Tyson Flax**

Unit No: **21**

Interval: **3673.00 ft (KB) To 3686.00 ft (KB) (TVD)**

Total Depth: **3686.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition: **Good**

Reference Elevations: **2120.00 ft (KB)**

2115.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 8320 **Inside**

Press@RunDepth: **123.15 psig @ 3674.00 ft (KB)**

Start Date: **2007.06.07**

End Date:

2007.06.08

Start Time: **20:13:12**

End Time:

03:08:40

Capacity: **7000.00 psig**

Last Calib.: **2007.06.08**

Time On Btm: **2007.06.07 @ 22:30:25**


Time Off Btm: **2007.06.08 @ 01:30:25**

TEST COMMENT: **IFP BOB in 8 min**

ISI Weak blow back built to 2 " died to 1/2 "

FFP BOB in 9 min

FSI Weak blow back built to 2 " died to 1"



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1879.68	103.22	Initial Hydro-static
1	26.59	103.19	Open To Flow (1)
16	54.30	115.80	Shut-In(1)
75	1153.21	112.16	End Shut-In(1)
75	59.39	112.01	Open To Flow (2)
121	123.15	117.64	Shut-In(2)
180	1105.62	116.68	End Shut-In(2)
181	1707.37	116.75	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
280.00	GCO 20%G 80%O	3.97
20.00	GMO 10%G 50%O 40%M	0.28
0.00	240' GIP	0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28335

DST#: 3

ATTN: Ed Glassman

Test Start: 2007.06.07 @ 20:13:10

Tool Information

Drill Pipe:	Length: 3660.00 ft	Diameter: 3.82 inches	Volume: 51.88 bbl	Tool Weight:	2500.00 lb	
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb	
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	40000.00 lb	
			Total Volume:	51.88 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	8.00 ft			String Weight: initial	32000.00 lb	
Depth to Top Packer:	3673.00 ft			Final	34000.00 lb	
Depth to Bottom Packer:	ft					
Interval between Packers:	13.00 ft					
Tool Length:	34.00 ft					
Number of Packers:	2	Diameter:	6.75 inches			
Tool Comments:						

Tool Description

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3653.00	
Shut In Tool	5.00			3658.00	
Hydraulic tool	5.00			3663.00	
Packer	5.00			3668.00	21.00 Bottom Of Top Packer
Packer	5.00			3673.00	
Stubb	1.00			3674.00	
Recorder	0.00	8320	Inside	3674.00	
Perforations	9.00			3683.00	
Recorder	0.00	13401	Inside	3683.00	
Bullnose	3.00			3686.00	13.00 Bottom Packers & Anchor
Total Tool Length:	34.00				



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28335

DST#: 3

ATTN: Ed Glassman

Test Start: 2007.06.07 @ 20:13:10

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

34 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 54.00 sec/qt

Cushion Volume:

bbl

Water Loss: 9.59 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3000.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
280.00	GCO 20%G 80%O	3.969
20.00	GMO 10%G 50%O 40%M	0.284
0.00	240' GP	0.000

Total Length: 300.00 ft

Total Volume: 4.253 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time





TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Poverty Oil LLC**

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

19 10 20 Rooks KS

Romine #3-19

Start Date: 2007.06.08 @ 10:10:08

End Date: 2007.06.08 @ 16:43:53

Job Ticket #: 28336 DST #: 4

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Poverty Oil LLC

2713 Ash St
Hays KS 67601

ATTN: Ed Glassman

Romine #3-19

19 10 20 Rooks KS

Job Ticket: 28336

DST#: 4

Test Start: 2007.06.08 @ 10:10:08

GENERAL INFORMATION:

Formation: **Arbuckle**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 11:33:08

Time Test Ended: 16:43:53

Test Type: Conventional Bottom Hole

Tester: Tyson Flax

Unit No: 21

Interval: **3690.00 ft (KB) To 3716.00 ft (KB) (TVD)**

Total Depth: 3716.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2120.00 ft (KB)

2115.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 8320

Inside

Press@RunDepth: 161.82 psig @ 3696.00 ft (KB)

Start Date: 2007.06.08

End Date: 2007.06.08

Start Time: 10:10:10

End Time: 16:43:53


Capacity: 7000.00 psig

Last Calib.: 2007.06.08

Time On Btm: 2007.06.08 @ 11:32:38

Time Off Btm: 2007.06.08 @ 14:32:23

TEST COMMENT: IFP BOB in 7 min
ISI Weak surface blow back built to 1.5 "
FFP BOB in 7 min
FSI Blow back built to 2 "



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1829.39	100.34	Initial Hydro-static
1	26.22	100.35	Open To Flow (1)
15	57.31	106.40	Shut-In (1)
74	1145.99	108.43	End Shut-In (1)
75	70.55	108.21	Open To Flow (2)
120	161.82	109.57	Shut-In (2)
180	1094.74	112.42	End Shut-In (2)
180	1773.59	112.65	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
50.00	HOCGM 10%G 30%O 50%M	0.71
360.00	CGO 20%G 80%O	5.10
0.00	240' GIP	0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28336

DST#: 4

ATTN: Ed Glassman

Test Start: 2007.06.08 @ 10:10:08

Tool Information

Drill Pipe:	Length: 3691.00 ft	Diameter: 3.82 inches	Volume: 52.32 bbl	Tool Weight: 2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight set on Packer: 25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose: 40000.00 lb
			Total Volume: 52.32 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	22.00 ft			String Weight: Initial 30000.00 lb
Depth to Top Packer:	3690.00 ft			Final 36000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	26.00 ft			
Tool Length:	47.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3670.00	
Shut In Tool	5.00			3675.00	
Hydraulic tool	5.00			3680.00	
Packer	5.00			3685.00	21.00 Bottom Of Top Packer
Packer	5.00			3690.00	
Stubb	1.00			3691.00	
Perforations	5.00			3696.00	
Recorder	0.00	8320	Inside	3696.00	
Perforations	17.00			3713.00	
Recorder	0.00	13401	inside	3713.00	
Bullnose	3.00			3716.00	26.00 Bottom Packers & Anchor

Total Tool Length: 47.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil LLC

Romine #3-19

2713 Ash St
Hays KS 67601

19 10 20 Rooks KS

Job Ticket: 28336

DST#: 4

ATTN: Ed Glassman

Test Start: 2007.06.08 @ 10:10:08

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

31 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 57.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.79 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 4000.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
50.00	HOCGM 10%G 30%O 50%M	0.709
360.00	CGO 20%G 80%O	5.103
0.00	240' GIP	0.000

Total Length: 410.00 ft

Total Volume: 5.812 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time

