

DRILL STEM TESTS FOR Towns # 1

DST # 1 3564-3614' , 30"-30"--30"-30" ; Weak First blow, Died 12"
No Blow 2nd Opening, Flushed tool, No help.
Recovered 10 ft. Drilling Mud with Few specks Oil
INFP 68-68#,, FFP, 82-82#
SIP 246-137#
HYD. Pressure 1796-1776#

DST # 2 3726-3740' 15"=20"--15"-20" . Strong blow throughout
both openings. Recovered 180' Gas in pipe,
700 ft Clean oil, 124' Mdy watery oil(75%oil)
124' M& GC Oily Wtr.(3% M,5% G,10% O,82% Wtr.)
124' As above(2% M,5% G, 5% O, 88% Wtr)
243% Salt Water, scum oil.
Tool Sample Grindout:72% oil, 27 % wtr. 1% mud

Pit Sample Mud: Vis. 47, Wt. 9.2, WL 8.4, Chlorides 3000 ppm.
By Tester