


15-163-23572

19-10s-20w



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Poverty Oil Company**

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

19 10S 20W Rooks KS

Romine #2-19

Start Date: 2006.12.05 @ 17:35:19

End Date: 2006.12.06 @ 01:05:19


Job Ticket #: 27582 DST #: 1

KCC
FEB 12 2007
CONFIDENTIAL

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

Poverty Oil Company

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

Romine #2-19

19 10S 20W Rooks KS

Job Ticket: 27582

DST#: 1

Test Start: 2006.12.05 @ 17:35:19

GENERAL INFORMATION:

Formation: **LKC**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 19:48:34

Time Test Ended: 01:05:19

Test Type: **Conventional Bottom Hole**

Tester: **Jason McLemore**

Unit No: **32**

Interval: **3465.00 ft (KB) To 3610.00 ft (KB) (TVD)**

Total Depth: **3610.00 ft (KB) (TVD)**

Hole Diameter: **7.80 inches** Hole Condition: **Good**

Reference Elevations: **2115.00 ft (KB)**

2110.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 6719 **Inside**

Press@RunDepth: **52.42 psig @ 3471.00 ft (KB)**

Start Date: **2006.12.05**

End Date:

2006.12.06

Start Time: **17:35:21**

End Time:

01:05:19

Capacity: **7000.00 psig**

Last Calib.: **2006.12.06**

Time On Btm: **2006.12.05 @ 19:48:19**

Time Off Btm: **2006.12.05 @ 23:08:04**


TEST COMMENT: **IFP Weak Blow Built to 3-1/2 "**

ISI Dead

FFP Weak Blow Built to 2 "

FSI Dead

Pressure vs. Time



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1682.91	91.15	Initial Hydro-static
1	17.65	90.65	Open To Flow (1)
31	37.56	92.28	Shut-In(1)
93	864.77	95.34	End Shut-In(1)
93	38.95	95.02	Open To Flow (2)
137	52.42	96.45	Shut-In(2)
200	784.18	98.92	End Shut-In(2)
200	1643.95	99.14	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
30.00	Water Out Mud 30%W 70%M	0.21
60.00	Mud	0.83

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27582

DST#: 1

ATTN: Ed Glassman

Test Start: 2006.12.05 @ 17:35:19


Tool Information

Drill Pipe:	Length: 3433.00 ft	Diameter: 3.80 inches	Volume: 48.16 bbl	Tool Weight:	2200.00 lb
Heavy Wt. Pipe:	Length: 31.00 ft	Diameter: 2.70 inches	Volume: 0.22 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	40000.00 lb
		Total Volume:	48.38 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	20.00 ft			String Weight: Initial	38000.00 lb
Depth to Top Packer:	3465.00 ft			Final	38000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	145.00 ft				
Tool Length:	166.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3445.00	
Shut In Tool	5.00			3450.00	
Hydraulic tool	5.00			3455.00	
Packer	5.00			3460.00	21.00 Bottom Of Top Packer
Packer	5.00			3465.00	
Stubb	1.00			3466.00	
Perforations	4.00			3470.00	
Change Over Sub	1.00			3471.00	
Recorder	0.00	6719	Inside	3471.00	
Blank Spacing	125.00			3596.00	
Change Over Sub	1.00			3597.00	
Perforations	10.00			3607.00	
Recorder	0.00	13221	Outside	3607.00	
Bullnose	3.00			3610.00	145.00 Bottom Packers & Anchor

Total Tool Length: 166.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27582

DST#: 1

ATTN: Ed Glassman

Test Start: 2006.12.05 @ 17:35:19

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 10.00 lb/gal

Cushion Length:

ft

Water Salinity:

23000 ppm

Viscosity: 60.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.76 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 4000.00 ppm

Filter Cake: 2.00 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
30.00	Water Out Mud 30%W 70%M	0.212
60.00	Mud	0.835

Total Length: 90.00 ft

Total Volume: 1.047 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:


DST Test Number: 1

19 10S 20W Rooks KS

Serial #: 6719 Inside Poverty Oil Company


Pressure vs. Time

6PM



Ref. No: 27582

Trilobite Testing, Inc



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Poverty Oil Company**

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

19 10S 20W Rooks KS

Romine #2-19

Start Date: 2006.12.06 @ 11:28:54


End Date: 2006.12.06 @ 19:03:09

Job Ticket #: 27583 DST #: 2

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Poverty Oil Company

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

Romine #2-19

19 10S 20W Rooks KS

Job Ticket: 27583

DST#: 2

Test Start: 2006.12.06 @ 11:28:54

GENERAL INFORMATION:

Formation: **Arbuckle**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 13:26:39

Time Test Ended: 19:03:09

Test Type: Conventional Bottom Hole

Tester: Jason McLemore

Unit No: 32

Interval: **3696.00 ft (KB) To 3707.00 ft (KB) (TVD)**

Total Depth: 3707.00 ft (KB) (TVD)

Hole Diameter: 7.80 inches Hole Condition: Good

Reference Elevations: 2115.00 ft (KB)

2110.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 6719

Inside

Press@RunDepth: 179.71 psig @ 3701.00 ft (KB)

Start Date: 2006.12.06

End Date:

2006.12.06

Capacity: 7000.00 psig

Last Calib.: 2006.12.06

Start Time: 11:28:56

End Time:

19:03:09

Time On Btm: 2006.12.06 @ 13:26:24

Time Off Btm: 2006.12.06 @ 16:30:24


TEST COMMENT: IFP Strong Blow BOB in 3 Min.

ISI Blow back Built to 8 "

FFP Good Blow BOB in 6 Min.

FSI

Pressure vs. Time



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1855.97	99.05	Initial Hydro-static
1	51.55	98.72	Open To Flow (1)
17	122.52	109.11	Shut-In (1)
81	196.35	109.15	End Shut-In (1)
81	127.06	109.12	Open To Flow (2)
122	179.71	110.60	Shut-In (2)
184	193.86	111.23	End Shut-In (2)
184	1726.30	111.65	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
35.00	MCO 50%O 50%M	0.27
400.00	SGO 20%G 80%O	5.61

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27583

DST#: 2

ATTN: Ed Glassman


Test Start: 2006.12.06 @ 11:28:54

Tool Information

Drill Pipe:	Length: 3653.00 ft	Diameter: 3.80 inches	Volume: 51.24 bbl	Tool Weight:	2200.00 lb
Heavy Wt. Pipe:	Length: 32.00 ft	Diameter: 2.70 inches	Volume: 0.23 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	60000.00 lb
			Total Volume: 51.47 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	10.00 ft			String Weight: Initial	36000.00 lb
Depth to Top Packer:	3696.00 ft			Final	39000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	11.00 ft				
Tool Length:	32.00 ft				
Number of Packers:	2	Diameter: 6.75 inches			
Tool Comments:					

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3676.00	
Shut In Tool	5.00			3681.00	
Hydraulic tool	5.00			3686.00	
Packer	5.00			3691.00	21.00 Bottom Of Top Packer
Packer	5.00			3696.00	
Stubb	1.00			3697.00	
Perforations	4.00			3701.00	
Recorder	0.00	6719	Inside	3701.00	
Perforations	3.00			3704.00	
Recorder	0.00	13221	Outside	3704.00	
Bullnose	3.00			3707.00	11.00 Bottom Packers & Anchor

Total Tool Length: 32.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27583

DST#: 2

ATTN: Ed Glassman

Test Start: 2006.12.06 @ 11:28:54

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

35 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 48.00 sec/qt

Cushion Volume:

bbf

Water Loss: 7.98 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 4000.00 ppm

Filter Cake: 2.00 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbf
35.00	MCO 50%O 50%M	0.269
400.00	SGO 20%G 80%O	5.611

Total Length: 435.00 ft

Total Volume: 5.880 bbf

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time





TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Poverty Oil Company**

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

19 10S 20W Rooks KS

Romine #2-19

Start Date: 2006.12.07 @ 01:10:18

End Date: 2006.12.07 @ 08:21:48


Job Ticket #: 27584

DST #: 3

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Poverty Oil Company

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

Romine #2-19

19 10S 20W Rooks KS

Job Ticket: 27584

DST#: 3

Test Start: 2006.12.07 @ 01:10:18

GENERAL INFORMATION:

Formation: **Arb**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 03:10:03

Time Test Ended: 08:21:48

Test Type: Conventional Bottom Hole

Tester: Michael Armbrister

Unit No: 32

Interval: 3708.00 ft (KB) To 3717.00 ft (KB) (TVD)

Total Depth: 3717.00 ft (KB) (TVD)

Hole Diameter: 7.80 inches Hole Condition: Good

Reference Elevations: 2115.00 ft (KB)

2110.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 6719

Inside

Press@RunDepth: 97.98 psig @ 3709.00 ft (KB)

Start Date: 2006.12.07

End Date:

2006.12.07

Capacity:

7000.00 psig

Last Calib.:

2006.12.07

Start Time: 01:10:20

End Time:

08:21:48

Time On Btm:


2006.12.07 @ 03:09:33

Time Off Btm:

2006.12.07 @ 06:14:03

TEST COMMENT: IF B of B 14 m
ISI 1/4 " Blow back died 20 m
FF B of B 20 m
FSI Surface blow back

Pressure vs. Time



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1815.09	94.82	Initial Hydro-static
1	16.48	94.84	Open To Flow (1)
16	44.11	106.64	Shut-In (1)
77	196.96	105.66	End Shut-In (1)
78	46.97	105.86	Open To Flow (2)
122	97.98	111.14	Shut-In (2)
185	193.70	110.14	End Shut-In (2)
185	1791.06	110.38	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
15.00	OCM 30%O 70%M	0.11
205.00	Clean Oil	2.76

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27584

DST#: 3

ATTN: Ed Glassman


Test Start: 2006.12.07 @ 01:10:18

Tool Information

Drill Pipe:	Length: 3686.00 ft	Diameter: 3.80 inches	Volume: 51.70 bbl	Tool Weight: 2200.00 lb
Heavy Wt. Pipe:	Length: 31.00 ft	Diameter: 2.70 inches	Volume: 0.22 bbl	Weight set on Packer: 20000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose: 40000.00 lb
		Total Volume: 51.92 bbl		Tool Chased 0.00 ft
Drill Pipe Above KB:	30.00 ft			String Weight: Initial 38000.00 lb
Depth to Top Packer:	3708.00 ft			Final 40000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	9.00 ft			
Tool Length:	30.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3688.00	
Shut In Tool	5.00			3693.00	
Hydraulic tool	5.00			3698.00	
Packer	5.00			3703.00	21.00 Bottom Of Top Packer
Packer	5.00			3708.00	
Stubb	1.00			3709.00	
Recorder	0.00	6719	Inside	3709.00	
Perforations	5.00			3714.00	
Recorder	0.00	13221	Outside	3714.00	
Bullnose	3.00			3717.00	9.00 Bottom Packers & Anchor
Total Tool Length:		30.00			



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27584

DST#: 3

ATTN: Ed Glassman

Test Start: 2006.12.07 @ 01:10:18

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 10.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 60.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.76 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 4000.00 ppm

Filter Cake: 2.00 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
15.00	OCM 30%O 70%M	0.106
205.00	Clean Oil	2.764

Total Length: 220.00 ft

Total Volume: 2.870 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:


Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time





DRILL STEM TEST REPORT

Prepared For: **Poverty Oil Company**

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

19 10S 20W Rooks KS

Romine #2-19

Start Date: 2006.12.07 @ 22:30:57


End Date: 2006.12.08 @ 07:16:40

Job Ticket #: 27585 DST #: 4

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Poverty Oil Company

2713 Ash Street
Hays KS 67601

ATTN: Ed Glassman

Romine #2-19

19 10S 20W Rooks KS

Job Ticket: 27585

DST#: 4

Test Start: 2006.12.07 @ 22:30:57

GENERAL INFORMATION:

Formation: **Arb**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 01:49:40

Time Test Ended: 07:16:40

Test Type: **Conventional Bottom Hole**

Tester: **Michael Armbrister**

Unit No: **32**

Interval: **3718.00 ft (KB) To 3744.00 ft (KB) (TVD)**

Total Depth: **3744.00 ft (KB) (TVD)**

Hole Diameter: **7.80 inches** Hole Condition: **Good**

Reference Elevations: **2115.00 ft (KB)**

2110.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 6719

Inside

Press@RunDepth: **295.79 psig @ 3719.00 ft (KB)**

Start Date: **2006.12.07**

End Date:

2006.12.08

Capacity: **7000.00 psig**

Last Calib.: **2006.12.08**

Start Time: **22:30:57**

End Time:

07:16:40

Time On Btm: **2006.12.08 @ 01:49:25**


Time Off Btm: **2006.12.08 @ 04:50:55**

TEST COMMENT: **IF B of B 6 m**

ISI dead

FF B of B 7 m

FSI dead



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2070.27	98.29	Initial Hydro-static
1	35.67	98.35	Open To Flow (1)
14	125.52	113.16	Shut-In(1)
79	758.81	112.11	End Shut-In(1)
79	176.23	111.78	Open To Flow(2)
121	295.79	115.55	Shut-In(2)
182	710.76	114.66	End Shut-In(2)
182	1754.38	115.28	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
180.00	SOCMW 3%O 17%W 80%M	2.31
400.00	SW	5.61

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27585

DST#: 4


ATTN: Ed Glassman

Test Start: 2006.12.07 @ 22:30:57

Tool Information

Drill Pipe:	Length: 3686.00 ft	Diameter: 3.80 inches	Volume: 51.70 bbl	Tool Weight:	2200.00 lb
Heavy Wt. Pipe:	Length: 31.00 ft	Diameter: 2.70 inches	Volume: 0.22 bbl	Weight set on Packer:	20000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	45000.00 lb
			<u>Total Volume: 51.92 bbl</u>	Tool Chased	4.00 ft
Drill Pipe Above KB:	20.00 ft			String Weight: Initial	35000.00 lb
Depth to Top Packer:	3718.00 ft			Final	40000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	26.00 ft				
Tool Length:	47.00 ft				
Number of Packers:	2	Diameter: 6.75 inches			
Tool Comments:					

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3698.00	
Shut In Tool	5.00			3703.00	
Hydraulic tool	5.00			3708.00	
Packer	5.00			3713.00	21.00 Bottom Of Top Packer
Packer	5.00			3718.00	
Stubb	1.00			3719.00	
Recorder	0.00	6719	Inside	3719.00	
Perforations	22.00			3741.00	
Recorder	0.00	13221	Outside	3741.00	
Bullnose	3.00			3744.00	26.00 Bottom Packers & Anchor
Total Tool Length:	47.00				



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Poverty Oil Company

Romine #2-19

2713 Ash Street
Hays KS 67601

19 10S 20W Rooks KS

Job Ticket: 27585

DST#: 4

ATTN: Ed Glassman

Test Start: 2006.12.07 @ 22:30:57

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 10.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 60.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.76 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 4000.00 ppm

Filter Cake: 2.00 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
180.00	SOCMW 3%O 17%W 80%M	2.310
400.00	SW	5.611

Total Length: 580.00 ft

Total Volume: 7.921 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time

