# Geological Report

American Warrior Inc.
Keller #3-6
1670' FSL & 1000' FEL
Sec. 6 T10S R20W
Rooks County, Kansas

James F Dilts
Geologist

RECEIVED
JUN 15 2009
KCC WICHITA

**American Warrior, Inc.**

## General Data

| | |
|---|---|
| Well Data: | American Warrior Inc.<br>Keller #3-6<br>SW-NE-SE<br>1670' FSL & 1000' FEL<br>Sec. 6 T.10S R.20 W.<br>Rooks County, Kansas<br>API # 15-163-23, 542-0000 |
| Drilling Contractor: | Duke Drilling Co |
| Spud Date: | 6/27/2006 |
| Rotary TD Date: | 7/1/2006 |
| Rotary TD: | 3966' |
| Elevation: | 2275' Ground Level<br>2371' Kelly Bushing |
| Casing: | Surface 222' 8 5/8" 23# surface casing set at 222' w/150 sx Common 3%cc 2%gel<br>Production 5.5" 14 # 3965' @ 3966' w/150 sx EA-2 ¼# Flocele |
| Samples: | 10' wet and dry, 2700' to RTD |
| Drilling Time: | 2700' to RTD |
| Electric Logs: | DIL/CDL//BHCS/CNL |
| Drillstem Tests: | None |
| Problems: | None |

RECEIVED
JUN 15 2010
KCC WICHITA

## Formation Tops

## Keller 3-6

| | |
|---|---|
| **Stone Corral** | **1750'+496** |
| **Topeka** | **3292'-1016** |
| **Heebner** | **3494'-1218** |
| **Toronto** | **3517'-1241** |
| **Lansing** | **3534'-1258** |
| **BKC** | **3756'-1480** |
| **Simpson** | **3788'-1512** |
| **Arbuckle** | **3838'-1562** |

Summary: Due to structural position and log information, the decision was made to case the Keller 3-6 for further evaluation

Respectfully Submitted,
James F Dilts

RECEIVED
JUN 15 2010
KCC WICHITA