

15-163-01994 ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REFINING CO.
Farm- Sutor "A" **No. 10**

SEC. 1 T. 10 R. 20w
SW NW SE

Total Depth. 3769'
Comm. 4-27-64 **Comp.** 5-6-64
Shot or Treated.
Contractor. Red Tiger Drilling Co.
Issued. 6-27-64

County **Rocks**
KANSAS



Elevation. 2231' DF

Production. 200 BOPD, NW

CASING:

8 5/8" 183' cem. w/150 sx.
 4 1/2" 3754' cem w/150 sx.

Figures Indicate Bottom of Formations.

sand	40
shale	183
shale & shells	780
shale	1110
sand	1410
shale	1655
Anhydrite	1691
shale & shells	1945
shale	2100
shale & lime	3400
lime	3768 RTD
lime ?	3769
Total Depth	

TOPS: LOG

Topeka	3220
Heebner	3423
Toronto	3441
Lansing Kansas City	3462
Base Kansas City	3692
Conglomerate	3702
Arbuckle	3754

DST #1 3578-3608 1/2 hrs. Good blow throughout test. Rec. 1201' gas in pipe. 3801' gassy, muddy oil, ISIP 370#/30", FSIP 345#/60" FP 90#-195#. HP 1980#-1980#. BHO 105 degrees F.

DST #2 3606-24 1/2 hrs., good blow through test, Rec. 587' muddy salt wtr. ISIP 1045#/30", FSIP: 775#/60" FP 100#-320#; HP 2015#-2010#, BHP 108 Degrees F.

DST #3 3626-47 1/2 Hrs., weak blow for 5" & died flushed tool in 0 hrs., no blow, Rec. 15' oil specked mud. ISIP 1095#/30", FSIP 585#/60"; FP 60#-60#, HP 2035-2030.

DST #4 3691-3717 1/2 hrs., weak blow for 5" & died, flushed tool in 1 hr., no blow, Rec. 30' slightly oil speck mud, ISIP 870#/30"; FSIP 155#/60"; FP 65#-65# HP 2100-2090, BHT 109 Degrees F.

DST #5 3754-68 1/2 hrs., good blow, gradually decreasing to fair blow throughout test. Rec. 638' gas in pipe. 2710' free oil. ISIP 1070#/30", FSIP 1070#/60" FP 430-1070#; HP 2145-2140.