

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY 15-163-00635
 508 East Murdock, Wichita, Kansas

Company- BARNETT OIL COMPANY
 Farm- Sparks "B" No. 1

SEC. 2 T. 10 R. 20W
 NE NE SW

Total Depth. 3832

Comm. 12-1-51


Comp. 12-13-51

Shot or Treated.

Contractor.

Issued. 7-11-53

County Graham
 KANSAS



CASING:

8 5/8" 171' com. w/ 125 sx
 5 1/2" 3828' com. w/ 125 sx

Elevation. 2245 KB

Production. 83 bbls. / no wtr

Figures Indicate Bottom of Formations.

surface shalo	40
sandy shalo	75
sand	105
sandy shale	125
shalo & sholls	168
shalo	365
shalo & sholls	1150
sand	1370
shale & sholls	1725
anhydrite	1763
shale & sholls	2230
limo & shalo	3265
limo	3786
chert limo	3810
limo	3832
Total Depth	

TOPS:

Heobner	3482
Lansing	3520
Base Kansas City	3730
Conglomerate	3767
Simpson Shale	3794
Arbuckle	3827

D.S.T. 3558-96' open 1 hr.
 weak blow thruout
 test 15 min. BHP
 Roc. 165' wtr

D.S.T. 3832.4 anchor packer
 at 3828' open 1 hr.
 weak blow at start,
 strong blow at finish.
 Roc. 180' free oil
 230' oil cut mud
 BHP 950#