

15-163-03142


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - HEATHMAN DRILLING CO., INC.
Farm - Glick No. 5

SEC. 4 T. 10 S. 20W
SE NE SE

Total Depth. 3785
Comm. 1-17-50 Comp. 1-30-50
Shot or Treated.
Contractor. Heathman
Issued. 3-18-50

County. Rocks KANSAS



Elevation. 2199(m)
2201 RB (2nd)

Production. 184 bbls.

CASING:
8 5/8" 114' cem w/100 sx.
5 1/2" 378 1/2' cem w/125 sx.

Figures Indicate Bottom of Formations.

shale sand	45
shale	570
shale, shells	835
sand, shale	1015
shale	1120
sand	1410
shale, red bed	1650
shale	1671
anhyd.	1722
shale, shells	2100
lime, shale	2290
shale, shells	2426
shale, lime	3250
lime	3309
lime, shale	3367
lime	3427
lime, shale	3465
lime	3744
conglomerate	3770
shale	3783
lime	3785
Total depth	

Tops: K.B.	
Anhydrite	1681
Topeka	3231
Heebner	3434
Lansing K.C.	3472
Conglomerate	3744
Simpson	3758
Arbuckle	3783 1/2
Rotary total depth	3785

Drilling-in data:

Drilled plug and made 1' new hole
to total depth. of 3786'; got
approx. 1 BOPH, bailed and cleaned
out and made 1/3 bailer oil each trip.
Shut down 1 hr, well filled up 80' in
1 hr.; bailed 1 2/3 BOPH for 4 hrs.
Gave 350 gal Dowell acid; swbd 3 BOPH,
1300' off bottom for 4 hrs., ran tubing
and rods. on Feb 5, 1950