

COMPANY HEATHMAN DRILLING CO., INC.

SEC. 4 T. 10 R. 20W


FARM Glick

NO. 6

LOC. NW SE SE

TOTAL DEPTH 3804
 COMM. 1-25-51 COMP. 2-5-51
 SHOT OR TREATED Acid 350 gals.
 CONTRACTOR Heathman Drllg Co., Inc.
 ISSUED 3-3-51

COUNTY Rooks



CASINO

8 5/8" 109' cem w/90 sx
 5 1/2" 3802' cem w/80 sx

ELEVATION

2227(m)

2228 D.F.

2230 RR Incl.

PRODUCTION

State Potential

480 BOPD, no water

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, shale 0-115
 shale 136
 shale, sand, shells 650
 shale, sand 1085
 sand 1090
 sand, shale 1710
 anhydrite 1751
 shale, shells 2365
 shale, lime 3017
 shale . 3157
 shale, lime 3252
 shale 3325
 lime, shale 3585
 lime 3653
 lime, shale RTD 3803
 lime & shale 3804
 Total Depth

Tops: KB
 Anhydrite 1710
 Topeka 3261
 Heebner 3460
 Lansing-K.C. 3499
 Base Kansas City 3723
 Conglomerate 3750
 Simpson 3778
 Arbuckle 3801

DST #1, 3565-85 - open
 30 min. recovered 260'
 salt water.

DST #2, 3783-3801 - packer
 failed, test unsuccessful,
 did not rerun.

Drilled plug and cleaned out
 to T.D. 3803 Slight show of
 oil.

DD - 1' to 3804 - filled
 800' oil 1st hr; 140 0' in 2nd hr.
 1580' in 3rd hr, 1680' in 4th hr.,
 1800' in 5th hr.

Swabbed 100' off bottom, 15 BO
 1st hr., 13 1/2 BO 2nd hr.