

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company - SINCLAIR OIL & GAS CO.
Farm - W. E. Baldwin No. 5

SEC. 5 T. 10 R. 20W

C S/2 SW SW
330' from S., 660
from W. lines SW $\frac{1}{4}$

Total Depth. 3892 PB 3862
Comm. 5-28-51 Comp. 6-10-51
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 7-28-51

County. Rooks
KANSAS



Elevation. 2272 RIG. FLOOR

Production. IPP 378 bbls.

CASING:

10 3/4" 186' cem w/175 sxs.
5 1/2" 3887 cem w/175 sxs.

Figures Indicate Bottom of Formations.

surface level measurement,
sand, shale 55
shale 187
shale, shells 375
shale, shells 1175
shale, sand 1245
sand 1365
shale, shells 1605
red bed, shale, shells 1755
anhydrite 1795
red rock, shale, shells 1980
shale, shells 2215
shale, lime, shells 2335
red rock, shale, shells 2370
shale, lime 3535
lime 3892
Total depth PB 3862

Tops:
Arbuckle 3837

Scout tops:
Topeka 3306
Heebner 3500
Toronto 3522
Lansing 3539
Conglomerate 3797
Simpson 3824

6-10-51 Ran Schlumberger at 3887.
Perforated Arbuckle lime 24
holes 3837-3841, swabbed 5 bbls.
an hr for 5/hrs.
Acidized 1500 gals. Swabbed
200 bbl. oil, no wtr, in 7 hrs.
State test 6-20-51 in 8 hrs.
pumped 126 oil, no wtr, for
pot. 378 bbls.