

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-163-04264


Company - SKELLY OIL COMPANY
Farm - Henry Beinke No. 1

SEC. 5 T. 10 R. 20W
NW NW SE
330' fr NL & 330' fr WL SE $\frac{1}{2}$

Total Depth. 3851'
Comm. 12-6-48 Comp. 12-31-48
Shot or Treated.
Contractor. Claude Wentworth Drilg. Co., Inc.
Issued. 4-9-49

County. Rooks

KANSAS



Elevation. 2249' *Ind*

CASING:
8-5/8" 413' Cem. W/175 Sx.
5-1/2" 3846' Cem. W/200 Sx.

Figures Indicate Bottom of Formations.

Production. 1st test POB 5 hrs. 50
BO, no wtr., after shot - POB
8 hrs. 197.20 BO no wtr.
to est. 24 hr SCC Pot. 592 bbls.

surface soil	10
shale & red clay	200
sand	300
redbed, shale & shells	413
shale & shells	830
sand	1200
shale & sand	1310
sand	1480
shale	2480
lime & shale	2865
lime	3005
lime & shale	3329
lime	3587
lime & shale	3628
lime	3675
shale	3705
lime	3824
dolo., buff fine to med.	
granular, slightly	
sandy	3829
dolomite sdy	3847
fine to me. xlyn	
dolomite	3848
dense dolomite	3855
SLM 3855 - 3850	
dolo. sdy brwn	3851
Total Depth	

Tops:

Heebner Shale	3490
Lansing Lime	3530
Conglomerate	3789 SLM
Simpson shale	3813 SLM
Simpson Dolomite	3819 SLM
Arbuckle Lime	3842 SLM

3530-35 lgt scattered sat.
3570-77 lgt scattered sat.
3 09-3619 fair por. & lgt sat.
3824-29 porr por. & lgt sat.
3842-3843 good por. & sat.
3850-51 Porous & saturated