

15-163-30329

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- GULF OIL CORPORATION  
Farm-Frank Hinkhouse No. 5

SEC. 6 T. 10 R.20W  
C SE SW NE

Total Depth. 3838  
Comm. 12-29-52 Comp. 1-24-53  
Shot or Treated. Acid: 500 gals. 1-14, 500 gals. 1-25  
Contractor.  
Issued. 6-27-53

County Rooks

KANSAS



Elevation. 2268 DF

Production. 208.5 BO, 6 BW

CASING:

8 5/8 set at 1786' w/ 725 sx cement  
5 1/2 set at 3836' w/ 100 sx cement

Figures Indicate Bottom of Formations.

surface clay & sand	145
sand & shale	350
shale & shells	920
sand & shale	1080
shale & shells	1220
sand & shale	1730
red bed & shells	1780
anhydrite	1815
shale & shells	2235
shale	2320
shale & shells	2495
lime & shale	2615
shale w/ lime streaks	2740
lime & shale	2970
lime w/ shale streaks	3075
lime & shale	3305
lime	3790
conglomerate	3838
Total Depth	

TOPS:

Heebner	3493	-
Toronto	3516	- 3526
Lansing	3535	
Arbuckle	3835	

Distance from RB to top of collar 6'

Production base on 8 hr. state test  
of 69½ BO, 2 BW