

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


15-163-02028

Company- HEATHMAN & COMPANY
Farm- Tucker No. 3

SEC. 6 T. 10 R. 20W
NW SE SE

Total Depth. 3862
Comm. 2-26-62 Comp. 3-10-52
Shot or Treated.
Contractor. Birmingham-Bartlett Drilling Co.
Issued. 5-24-52

County Rocks
KANSAS



CASING:
8 5/8" 152' cem w/125 sx
5 1/2" 3849' cem w/125 sx

Elevation. 2272
2269 (m)

Production. 108 bbls, no water

Figures Indicate Bottom of Formations.

clay, sand	40
sand	90
shale, shells	700
sand	1000
sand, shale, shells	1510
red bed, shells	1780
anhydrite	1820
shale, shells	2005
shale, lime	2960
shale, shells	3095
shale	3130
lime, shale	3190
lime	3473
lime, shale	3520
lime	3700
shale, lime	3738
lime	3799
lime, shale	3846
shale	3848
arbuckle	3851
shale	3862
Total Depth	

Tops:	
Anhydrite	1782 Schlumberger
Topeka	3291 Sample & Schl.
Heebner	3495 " " "
Toronto	3518 " " "
Lansing	3535 " " "
Base K.C.	3758 " " "
Conglomerate	3795 " " "
Simpson	3826 " " "
" Sand	3828-30 " " "
" Dolomite	3836-41 " " "
Arbuckle	3846 " " "

Penetration 5 1/2'

Total Depth 3851 1/2

Drilling-In Information:

Plug Drilled & well DD 3855

Acidized w/500 gal-

well swabbed 1 boph

Acidized w/1000 gal.

well swabbed 2 boph

After 2000 gal. more acid,

there was no increase.

Drilled deeper 3860

1000 gal. acid brought no

increase in oil.

Drilled deeper to 3862 T.D.

where there was an increase

of about 1/2 to 1 boph, making

a total of 2 1/2 to 3 boph with

a slight show of water.

Tested 16 hrs by swab, averaged

2 1/2 boph, very small amount of

water. put on pump.