

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-03226

Company- D.G. HANSEN
Farm- Wolf

No. (1) 3

SEC. 6 T. 10 R. 20W
SE NW NW

Total Depth. 3870'

Comm. 6-4-56


Comp. 6-15-56

Shot or Treated.

Contractor.

Issued. 12-1-56

County Rocks
KANSAS



Elevation. 2289' DF

Production. 108 BOPD Pot.

CASING:

8 5/8" 167'

5 1/2" 3864'

All Meas. fr RB

Figures indicate Bottom of Formations.

surface soil	167
shale	325
shale-sand	1240
shale	1300
sand	1525
red bed	1779
anhydrite	1819
shale	1925
lime-shale	3867 RTD
lime-shale	3870
Total Depth	

TOPS:

Anhydrite	1779
Topeka	3317
Heebner	3520
Toronto	3545
Lansing	3561
B/Kansas City	3781
Conglomerate	3831
Simpson	3847
Arbuckle	3862

DST #1 - 3638-49 Weak blow
for 10 min. Rec. 15' very
slightly OCM & 0% BHP. De-
cided we had a plugged tool
& ran again. Very strong blow
through test. Rec. 1220' gas,
1730' fluid, of which 1700'
was clear oil & rest muddy
oil 1100% BHP 175# IFP & 830#
BHP.

DST #2 - 3747-3763 Open 1 hr.
w/weak blow for 7 min. Rec. 40'
watery slightly OCM & 1145 #BHP.

DST #3 - 3765-74 Open 1/2 hr.
w/weak blow less than 1 min.
Rec. 2' mud & 0% BHP cleaned out
total depth & drilled deeper to
3870. Swabbed 1 BOPH. Acidized
w/500 gals. Swabbed 1 1/4 BOPH.