

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-03225


Company. D. G. HANSEN
Farm. Wolf

No. 2

SEC. 6 T. 10 R. 20W
SE NE NW

Total Depth. 3869
Comm. 5-23-56 Comp. 6-3-56
Shot or Treated. 500 gal acid.
Contractor. C-G Drilling Co.
Issued. 8-18-56

County Rocks
KANSAS



CASING:
8 5/8 170'
5 1/2 3863'

Elevation. 2272 DF

Production. 80 BOPD

Figures indicate Bottom of Formations.

surface soil	170
shale	690
sand	760
shale	940
sand	1030
shale	1360
sand	1505
red bed	1764
anhydrite	1803
shale & sand	2040
lime & shale RTD	3868
lime & shale	3869
Total Depth (RBM)	

TOPS: (RBM)	
Anhydrite	1764
Topeka	3312
Heebner	3514
Toronto	3538
Lansing	3554
Base KC	3777
Conglomerate	3832
Simpson	3850
Arbuckle	3862

DST #1: 3631-41, open 1 hr. mod good
bl. thruout, rec. 380' SW, FFP 200#,
BHP 1150#.

DST #2: 3863-68, open 1 hr. good bl.
thruout, rec. 240' gas, 250' fluid,
(220' oil, 30' muddy oil) FFP 80#,
BHP 420#