

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15

163

County

21329

Number

WICHITA BRANCH

Operator

PETROLEUM, INC.

Address

Suite 800, 300 West Douglas, Wichita, Kansas 67202

Well No.

5

Lease Name

Temple 'B'

Footage Location

2310 feet from (N) (S) line

520 feet from (E) (W) line

Principal Contractor

DNB Drilling, Inc.

Geologist

John Emerson

Spud Date

6-8-81

Date Completed

6-18-81

Total Depth

3860'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser


S. 7 T. 10 R. 20 E

Loc. 140' W. C. N/2 NW SW

County Rooks Co., Kansas

640 Acres

N



Locate well correctly

2219

Elev.: Gr.

DF 2221

KB 2224

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	287'	Common	175	2% Gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 216-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator PETROLEUM, INC.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole	
Well No. 5	Lease Name Temple 'B'		
S 7 T 10 R 20 SE W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	
			NAME
			DEPTH
DST #1 3408-3452' 15-30-60-120 Rec 450' muddy water, IFP 86-97, ISIP 1113, FFP 141-250, FSIP 1103			E.L. TOPS
			Anhydrite 1728
			Heebner 3463
DST #2 3541-3585' 15-30-60-120 Rec. 65' oil cut mud, 60' watery oil cut mud, 60' slightly oil cut water. IFP 65-65, ISIP 391, FFP 86-119, FSIP 391			Lansing 3503
			B/Kansas City 3722
			Arbuckle 3793
DST #3 3687-3730' 15-30-30-60 Rec. 10' mud. IFP 54-54, ISIP 478, FFP 54-54, FSIP 478			
DST #4 3799-3805' 15-30-30-60 Rec. 5' mud. IFP 21-21, ISIP 163, FFP 43-43, FSIP 143			
DST #5 3804-3815' 15-30-30-60 Rec 10' oil specked mud. IFP 43-43, ISIP 185, FFP 43-65, FSIP 207			
DST #6 3814-3825' 15-30-30-60 Rec 20' oil specked drilling mud. IFP 32-32, ISIP 260, FFP 32-32, FSIP 228			
DST #7 3825-3835' 15-30-30-60 Rec. 70' watery mud w/few oil specks. IFP 43-43, ISIP 282, FFP 65-65, FSIP 282			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Exploration Manager Title 6-29-81 Date		

11621