


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - H. LATHMAN DRG. CO.
Farm - Rode No. 3

SEC. 9 T. 10 R. 20W
SW SE SW

Total Depth. 3810
Comm. 5-10-50 Comp. 5-19-50
Shot or Treated. 6000 az.
Contractor. Birmingham-Bartlett Drlg.
issued. 7-8-50

County. Rooks
KANSAS



Elevation. 2226 R.B. Incl.

Production. 337 bbls.

CASING:

8 5/8" 149' cem. w/125 sx.
5 1/2" 3795' cem. w/125 sx.

Figures Indicate Bottom of Formations.

surface	149
shale	885
sand & shale	950
shale	1135
sand & shale	1250
sand	1330
shale & red bed	1709
anhyd.	1748
shale & shells	1855
shale	2160
shale & shells	2325
shale, lime shells	2385
lime	2465
lime & shale	2555
shale & lime shells	2635
shale & shells	2875
shale	3245
shale & lime	3400
lime	3787
S. shale	3792
Arbuckle R.T.D.	3795
lime	3810
Total Depth -	

Tops: Scout

Anhyd.	1709
Heebner	3463
Lansing	3505
Congl.	3757
Simpson	3775
Arbuckle	3792