

15-163-70161

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas


Company - HEATHMAN DRILLING CO., INC.
Farm - Selina-Veatch "A" No. 2

SEC. 9 T. 10 R. 20W
SW-SE-NW

Total Depth. 3788
Comm. 2-3-50 Comp. 2-16-50
Shot or Treated.
Contractor. Heathman Drilling Co., Inc.
Issued. 4-8-50

County. Rooks

KANSAS



CASING: 8 5/8" 144' w/100 sx
5 1/2 3787' w/125 sx

2214 (m)

Elevation. 2216 RB (2nd)

Production. 2647 Pot.

Figures Indicate Bottom of Formations.

Sand & shale	50
Sand & shale	146
Shale	545
Shale & sand	1395
Shale & shells	1602
Shale - Red bed	1711
Anhydrite	1720
Anhydrite	1740
Shale	1855
Shale & shells	2105
Shale	2260
Shale & lime	2480
Shale & shells	2577
Shale & lime	3236
Shale	3250
Lime & shale	3524
Lime	3700
Lime & shale	3741
Lime, shale & Cong.	3783
Shale & lime	3788
Total Depth	

Tops: KB

Anhydrite	1711
Topeka	3249
Hobner	3452
Lansing-Kansas City	3490
Base Kansas City	3714
Conglomerate	3742
Simpson	3759
Arbuckle dolomite	3785

2-21-50 - Drilled plug, gave
500 acid; swabbed 10 boph -
1st hr. 1300' off bottom;
swabbed 14 boph - 2nd hr. 1800'
off bottom; swabbed 16 boph -
3rd hr. 2200' off bottom.
Putting on pump.