

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - BARNETT OIL CO.

Farm - Sparks

No. 2

SEC. 10

T. 10

R. 20W

NE SW NE

Total Depth. 3846 PB 3830½

Comm. 4-15-51

Comp. 5-12-51


Shot or Treated.

Contractor.

Issued. 7-28-51

County. Rooks

KANSAS



CASING:

8 5/8" 14½ ccm w/125 sxs.
5" 3816

Elevation. 2216

2248 RB (and)

Production. IPP 12 B0, &
trace wtr.

Figures Indicate Bottom of Formations.

surface clay	25
sand	35
shale, shells	880
sand	1120
shale, shells	1716
anhydrite	1755
shale, shells	2085
shale, lime	2385
lime	2530
lime, shale	3055
shale	3200
shale, lime	3525
lime	3819
finely xlyn dolomite	3821
dolomite, chert	3823
dolomite	3831
lime	3833
gr. , yellow shale & some dolomite	3834
xlyn dolomite	3835½
very shaley	3836½
red, gr., yellow shale	3837½
shale, lime	3838½
lime	3840½
lime, shale	3846
Total depth PB 3830½	

Scout tops:

Topeka	3279
Heebner	3482
Lansing	3518
Base Kansas City	3736
Conglomerate	3789
Simpson	3812
Arbuckle	3815