


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- COOK & GALLOWAY DRILLING CO.
Farm- Croffoot No. 10

SEC. 11 T. 10 R. 20W
SE NE SW

Total Depth. 3777
Comm. 1-9-57 Comp. 1-23-57
Shot or Treated.
Contractor. C-G Drlg Co.
Issued. 3-16-57

County Rocks
KANSAS



CASING:
8 5/8" 174.23' cem w/175 sx. Circ.
4 1/2" 3789.81' cem w/125 sx.

Elevation. 2240 RB

Production. 147 BOPD

Figures indicate Bottom of Formations.

rat hole	0 -	125
cement		174
Drlg plug	175 -	550
shale, sand		1485
red bed		1676
anhydrite		1713
shale		1800
shale, lime		3285
lime		3300
lime, shale		3500
lime		3519
lime, shale		3593
lime		3631
lime, shale		3655
Reaming	3655-59	
lime, shale		3685
lime		3701
lime, shale		3721
lime		3777
Total Depth		

Tops: Scout	
Anhydrite	1676
Topeka	3249
Heebner	3454
Toronto	3476
Lansing	3492
Base Kansas City	3705
Simpson	3754
Arbuckle	3773

Drill Stem Test:
#1 3274-85 IF 20 min. Open
1 hr. Shut in 02 mins.
Rec. 100' muddy salt
water, BHP 980#.

3479 twisted off 34 strands
down hole. Fishing.

Electric log run.