

15-163-03527

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SOHIO ET AL

SEC. 12 T. 10 R. 20W

FARM Desbien


NO. 2

LOC. SW SW NE

TOTAL DEPTH 3760
 COMM. 11-11-50 COMP. 11-25-50
 SHOT OR TREATED
 CONTRACTOR R.W. Rine Drilling Co.
 ISSUED 1-6-51

COUNTY Rooks

KANSAS



CASING

8 5/8" 1632½' cem w/150 sx.
 5 1/2" 3757' cem w/150 sx.

ELEVATION 2224 2d.

PRODUCTION DD 16,204 BOPD

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, clay 40
 sand, clay, shale 600
 shale, sand, shells 1100
 sand Dakota 1290
 shale, shells 1624
 anhydrite 1634
 Drilled cement 1600-34
 anhydrite, red bed 1665
 shale, shells 2320
 shale, lime 2850
 lime 2940
 shale, lime 3303
 lime 3320
 lime, shale 3360
 lime 3483
 lime cherty 3655
 lime 3677
 lime, shale 3757
 lime Arbuckle 3760
 Total Depth

Tops:

Anhydrite 1624
 Topeka 3225
 Heebner 3428
 Lansing 3463
 Arbuckle 3757