

15-163-02071


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 S. Burdock Wichita, Kansas

Company - GULF OIL CORP  
Farm - Earl Sutor No. 1

SEC. 12 T. 10 R. 20W  
SE SE SE

Total Depth. 3776  
Comm. 11-18-49 Comp. 12-12-49  
Shot or Treated. Acidized with 500 gallons 12-10-49  
Contractor.  
Issued. 2-11-50

County. Roots  
KANSAS



CASING:  
8 5/8 set @ 1659' com w/ 675 sxs  
5 1/2 set @ 3774' com w/ 100 sxs

Elevation. 2223 feet.

Production. 74 bbls oil, no wtr

Figures Indicate Bottom of Formations.

shale and shells	1110
shale and shells	1345
anhydrite	1664
shale and shells	1895
salt and shale	2085
shells and shale	2175
lime	3055
lime and shale	3489
lime	3725
shale and sand	3776
Total Depth	

TOPS:	
Heebner	3432
Lansing	3468
P/B.C.	3702
Simpson	3755
Arbuckle	3773

Top 5 1/2" collar 9' below rotary bushing.

acidized with 500 gallons 12-10-49

Sand Record-- Arbuckle  
3773-3776