

15-163-19010


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East ~~Murdock~~, Wichita, Kansas

Company - GULF OIL CORP.
Farm - Earl Sutor No. 3

SEC. 12 T. 10 R. 20W
NW SW SE

Total Depth. 3773
Comm. 7-1-50 Comp. 8-6-50
Shot or Treated. Acid 1500 gals.
Contractor.
Issued. 9-16-50

County. Rooks
KANSAS



CASING:
8 5/8" 1657' cem w/675 sx.
5 1/2" 3766' cem w/100 sx.

Elevation. 2232 KB

2227.2nd.

Production. "P" 4604 BO, no wtr.
Pot, based on 3 stages state
DD test.

Figures Indicate Bottom of Formations.

surface hole, sand, shale	335
shale	380
clay, shale	465
shale, shells	1120
sand	1270
shale, shells	1595
anhydrite	1695
shale, shells, red bed	1960
shale, shells	2030
shale, salt	2140
shale, shells	2535
lime	2885
shale	3315
shale, lime	3405
lime	3773
Total Depth	

Tops:

Heebner	3437
Toronto	3459
Lansing	3496
PBC	3707
Viola	3716
Simpson	3747
Arbuckle	3765

Distance H: Top collar 5 1/2"
casing to rotary bushing is 7'