

15-163-02077

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY GULF OIL CORPORATION

SEC. 12 T. 10 R. 20

FARM Earl Suter

NO. 7

LOC. SE NE SE

TOTAL DEPTH 3766

COMM. 12-2-50

COMP. 12-24-50


SHOT OR TREATED Acid: 1,500

CONTRACTOR

ISSUED 2-10-51

COUNTY Rooks

KANSAS



CASING

8 5/8" 1655' cem. w/675 sx
 5 1/2" 3761' cem. w/100 sx

ELEVATION

2227 Ind.
2226'

PRODUCTION

3,413 bbls.
 drawdown test
 no wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & shells	1125
shale & sand	1265
shale & shells	1530
shale & red bed	1575
shale	1645
shale & anhydrite	1659
anhydrite	1670
red bed, shale and shells	2130
shale & shells	2355
lime	2450
lime & sandy lime	2660
shale & lime	3165
shale	3320
lime RTD	3763
deepened with cable tools to lime	3766
Total Depth	3766

Tops:

Heebner	3425
Toronto	3442
Lansing	3461
BKC	3678
Pennsyl. Basal Congl.	3703
Viola	3725
Simpson	3738
Arbuckle	3760